VARIANCENOTE

V07-01 PORTER STREET NEAR GILMER ST FREDDY TEEMS (TY MITCHAM, rep.) 0.60 APPROVED 1-22-07

Allow for new light industrial development by eliminating buffer along Porter St. reduce buffer and setback to 20 ft.

in rear yard, reduce buffer and setback to 15 ft. in both side yards

*** BUFFER REQUIREMENTS *** ANY BUFFER ENCROACHMENT DURING CONSTRUCTION THAT IS NOT SHOWN ON THE APPROVED SITE PLANS, LIKE UTILITY INSTALLATION, REOUIRES THAT REVISED PLANS BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO PROCEEDING WITH THE ENCROACHMENT ACTIVITY.

Accepted plans and subsequent accepted revisions must be on-site at all times

Accepted of these Plans by the CITY does not relieve permit holder from meeting all requirements of the 'CITY OF CARTERSVILLE ZONING ORDINANCE', 'FLOOD DAMAGE PREVENTION ORDINANCE', 'SOIL EROSION AND SEDIMENTATION CONTROL ORDINANCE', THE RULES AND REGULATIONS OF THE BARTOW COUNTY HEALTH DEPARTMENT, THE US ARMY CORPS OF ENGINEERS AND ANY OTHER LOCAL, STATE, OR FEDERAL LAW OR REGULATIONS as it relates to development in THE CITY OF CARTERSVILLE.

The location of erosion and sediment control devices may have to be altered from that shown on the accepted plans due to changes in drainage patterns created during construction. It is the owner/developer's responsibility to accomplish erosion and sediment control for all drainage patterns created at various stages during construction. Any difficulty in controlling erosion or sediment during any phase of construction shall be reported to the project engineer immediately. FAILURE TO PROPERLY INSTALL, OPERATE OR MAINTAIN ALL EROSION AND SEDIMENTATION CONTROL MEASURES MAY RESULT IN ALL CONSTRUCTION BEING STOPPED UNTIL SUCH MEASURES ARE CORRECTED TO THE SATISFACTION OF THE CITY OF CARTERSVILLE INSPECTOR.

Owner agrees by implementation of these plans that all land clearing, construction, development and drainage activities will be done according to these accepted plans or previously accepted revisions. Owner acknowledges that acceptance of plans by the City in no way relieves owner of responsibility not to adversely impact downstream property regarding any land disturbing activity, erosion and sediment control measure and or stormwater management activity during or after construction. Owner acknowledges that the acceptance of these plans and the issuance of the Land Disturbance Permit does not in any way suggest that all other requirements for the legal or appropriate operations for this activity, which may require additional permitting, have been met. The onus is on the owner/developer to discover what additional permitting or approvals may be necessary if any to operate from his point in an appropriate and legal manner. Plan acceptance or permit issuance does not absolve the applicant laws, policies, standards or other permits which may be required for this project.

Any and all land disturbance permits may be revoked at anytime if the construction of project is not in strict accordance with accepted plans. If actual site conditions vary from accepted plans, it is the owner/developers responsibility to inform the engineer of record and the city zoning administrator for assessment of condition. Project construction may be delayed during assessment period.

Acceptance and/or subsequent acceptance of these plans does not constitute approval by THE CITY OF CARTERSVILE of any land disturbing activities within wetland areas, Jurisdictional Water of the State, areas of threatened/endangered species, or areas of Historical Significance. It is the owner's responsibility to contact the appropriate regulatory agency for any required approvals.

Developer shall furnish, install and maintain all necessary traffic barricades and warning signage to the satisfaction of the Public Works Department while roadway frontage improvements are made.

Owner/Developer is responsible for maintaining control of silt on-site at all times. Developer is also responsible for control of silt that is tracked onto County R/W or subdivision streets by builders, contractors, subcontractors, utility companies or any other during construction until street has been accepted by City Public Works Department.

Maintain a minimum of 2' of cover over storm pipes. All corrugated metal pipe to be maintained by county shall be fully asphalt coated. Paved inverts are required in perennial streams. Pipe gage determined based on depth of cover and loading conditions.

The burying of construction debris, cleared trees and shrubs, and similar by-products of development is strictly prohibited. All solid waste, demolition debris and construction debris generated from construction must be properly disposed of in the Bartow County Landfill. Storm water detention facility(ies) shall remain in place as approved and as-built certified in perpetuity and shall not be encroached upon for any reason

Detention facility(ies) shall be inspected on a semi-annual basis by owner. Any accumulated trash, sediment, or debris shall be removed and disposed of in an approved manner.

Owner/Developer shall accept full liability for the safety of all persons in or around the detention facility(ies) at all times.

Owner/Developer shall indemnify county against all suits brought about by the existnece of the detention facility(ies).

Owner/Developer shall provide that oblicgations be transferred to all successors and assigns of property, and shall accept responsibility for informing such successors and assigns of said obligations.

All existing and proposed storm drainage features affecting this development have been evaluated and/or designed in accordance with current CITY OF CARTERSVILLE requirements and will not adversely impact any proposed on-site improvements or upstream or downstream property.

> *** STREET SIGNS *** DEVELOPER TO PROVIDE ALL SIGNAGE TO MUTCD STANDARD *** WASTE MATERIALS *** WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

*** OFF-STREET PARKING *** OFF-STREET PARKING MUST BE PROVIDED AND MAINTAINED THOUGHTOUT CONSTRUCTION

*** LAND DISTURBING ACTIVITIES *** LAND DISTURBING ACTIVITIES UNDER THE PERMIT MUST BEGIN WITHIN 120 DAYS AFTER ISSUANCE OF THE LAND DISTURBANCE PERMIT

CONSTRUCTIO	JNI SO	"HFD	/ F					
Note: Construction schedule is a general timeline from date the land disturbance permit is issued.								
ACTIVITY Month 1 Month 2 Month 3 Month 4 Month 5 Month 6								
COMMENCEMENT OF CONSTRUCTION	1							
INITIAL EROSION CONTROL BMP INTSALLATION	Z							
CLEARING GRUBBING & GRADING								
INTERMEDIATE EROSION CONTROL BMP'S								
GRASSING								
MAINTAIN SEDIMENT CONTROL MEASURES								
INSTALL UNDERGROUND UTILITIES								
INSTALL PAVING								
BUILDING CONSTRUCTION								
FINAL LANDSCAPING								
FINAL PHASE OF ERO. AND SED. CONTROL PLAN								
COMPLETION OF CONSTRUCTION						l		

10-2-18	REVISED PER CITY OF CARTERSVILLE COMMENTS
9-18-18	REVISED PER CITY OF CARTERSVILLE COMMENTS
DATE	REVISION

*****WATER & SEWER NOTE*****

THE OWNER/DEVELOPER SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH ESTABLISHING WATER AND SEWER SERVICE TO THE DEVELOPMENT. ADJUSTMENTS AND ADDITION TO THE WATER AND SEWER PIPING SHOWN ON THESE PLANS MAY BE NECESSARY TO ACCOMMODATE DIFFERENCES IN

EXISTING UTILITIES ENCOUNTERED IN THE FIELD OR DUE TO NEEDED MODIFICATIONS DETERMINED AT THE TIME OF CONSTRUCTION. THE OWNER/DEVELOPER SHALL BE

RESPONSIBLE FOR ANY NECESSARY RELOCATIONS, REPAIRS, OF IMPROVEMENTS TO THE EXISTING WATER AND SEWER

UTILITIES MADE NECESSARY BY THE CONSTRUCTION OF THIS PROJECT WHETHER IDENTIFIED ON THE PLANS OR NOT.

*** U.S. ARMY CORPS OF ENGINEERS*** IS THE DEVELOPER'S RESPONSIBILITY TO ADDRESS ANY WETLANDS ISSUES TO THE SATISFACTION OF THE U.S. ARMY CORPS OF ENGINEERS

*** U.S. FISH & WILDLIFE SERVICE *** ISSUES TO THE SATISFACTION OF THE U.S. FISH AND WILDLIFE SERVICE.

***** NPDES PERMIT REQUIREMENTS ***** IT IS THE DEVELOPER'S RESPONSIBILITY TO ABIDE BY ALL THE RULES AND GULATIONS PERTAINING TO THE STATE OF GEORGIA'S NATIONAL POLLUTAN DISCHARGE ELIMINATION SYSTEM (NDPES) PERMIT REQUIREMENTS.

SITE NOTES

- 1. ALL WORK WILL COMPLY WITH APPLICABLE STATE, FEDERAL, AND LOCAL CODES SPECIFICATIONS AND REQUIREMENTS. ALL NECESSARY LICENSES AND PERMITS SHALL BE OBTAINED BY THE CONTRACTOR AT HIS EXPENS
- 2. DEVIATIONS FROM THESE PLANS AND NOTES WITHOUT PRIOR CONSENT OF THE OWNER, HIS REPRESENTATIVE, OR THE ENGINEER MAY CAUSE THE WORK TO BE UNACCEPTABLE
- 3. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO COVER A COMPLETE PROJECT READY TO USE. ALL ITEMS NECESSARY FOR A COMPLETE AND WORKABLE JOB SHALL BE FURNISHED AND INSTALLED. THIS WILL INCLUDE ALL STRIPING AND PARKING LOT SIGNAGE
- 4. CONTRACTOR SHALL FURNISH AND MAINTAIN ANY AND ALL NECESSARY BARRICADES AROUND THE WORK AND PROVIDE PROTECTION AGAINST WATER DAMAGE AND SOIL EROSION
- 5. BOUNDARY INFORMATION SHOWN ON THIS PLAN WAS TAKEN FROM SMITH AND SMITH LAND SURVEYORS
- 6 ALL BUILDING DIMENSIONS SHALL BE CHECKED AND COORDINATED WITH THE ARCHITECTURAL PLANS.
- 7. FOR OTHER CONSTRUCTION DETAILS, SEE DETAIL SHEETS.
- 8. ALL SITE DIMENSIONS ARE TO THE FACE OF CURB/EDGE OF PAVEMENT EXCEPT WHERE NOTED.
- 9. ALL WORK ON SITE MUST CONFORM TO THE CITY OF CARTERSVILLE STANDARDS.
- 10. SEE DETAILS FOR PAVING SECTIONS.
- 11. PAVEMENT MARKINGS, INCLUDING STANDARD HANDICAP SYMBOLS. PARKING STRIPING AND TRAFFIC ARROWS, SHALL BE PAINTED ON PAVEMENT AT LOCATIONS SHOWN. SEE PAVEMENT MARKING DETAIL
- 12. SITE CONTRACTOR TO VERIFY EXISTING TOPOGRAPHIC AND UTILITY DATA PRIOR TO ANY CONSTRUCTION.
- METERS, AND OTHER UTILITIES IN VULNERABLE TRUCK AREAS.
- 14. WARRANTY: THIS SUBCONTRACTOR SHALL WARRANT ALL ASPHALT AGAINST ALL DEFECTS IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF TWO (2) YEARS.
- WETLANDS: 1. ACCEPTANCE OF THESE PLANS DOES NOT CONSTITUTE APPROVAL BY CITY OF CARTERSVILLE OF ANY LAND DISTURBING ACTIVITIES WITHIN WETI AND AREAS. IT IS THE OWNERS RESPONSIBILITY TO CONTACT THE APPROPRIATE REGULATORY AGENCY FOR APPROVAL OF ANY WETLAND AREA DISTURBANCE.
- 2. THERE ARE NO WETLANDS LOCATED ON-SITE. THEREFORE, NO PERMITS ARE REQUIRED

HE HOLDER OF THIS DOCUMENT WAIVES ALL CLAIMS AGAINST STEPHENSON ENGINEERING INCORPORATED FOR ANY UNAUTHORIZED CHANGES OR REUSE OF THIS DOCUMENT. THIS DOCUMENT IS AN INSTRUMENT OF SERVICE OF STEPHENSON ENGINEERING INCORPORATED FOR ANY UNAUTHORIZED CHANGES OR REUSE OF THIS DOCUMENT. THIS DOCUMENT. THIS DOCUMENT IS AN INSTRUMENT OF SERVICE OF STEPHENSON ENGINEERING INCORPORATED WHO RETAINS ALL RIGHTS OF COMMON LAW. STATUTE AND COPYRIGHT THERETO.

DEVELOPMENT/CONSTRUCTION PLANSFOR:

Freddy ⁻	Teems
Office Wa	irehouse
Porter S	treet

Located in Land Lot 339, 4th District, 3rd Section City of Cartersville

Bartow County, GA

OWNER/DEVELOPER

Freddy Teems 24 Hour Contact: Freddy Teems 30 Amberidge Drive Cartersville, Ga 30121 Phone: (770) 382-8166

City of Cartersvil	lle Site Plan Approval						
n accordance to the City of Cartersville Development Regulations and							
the City's Zoning Ordinance, all requirements of approval have been							
ulfilled; These Site Plans were giv	en final approval by the following City						
personnel on behalf	of the City of Cartersville:						
as System	Date						
lectric System	Date						
ibercomm	Date						
ire Department	Date						
1							
lanning and Development	Date						
ublic Works	Date						
Vater Department	Date						

UTILITYNOTES

- ANCHOR COLLARS SHALL BE PROVIDED ON STORM AND SANITARY SEWER LINES WHOSE
- SLOPE EXCEED 25% WATER METER AND WATER TAP SHALL BE RAISED AS NECESSARY TO BE FLUSH WITH NEW FINISH GRADES.
- TOPS OF EXISTING MANHOLES SHALL BE RAISED AS NECESSARY TO BE FLUSH WITH NEW FINISH GRADES.
- CONTRACTOR IS TO COORDINATE INSTALLATION OF GAS LINES WITH LOCAL GAS COMPANY. CONTRACTOR SHALL COORDINATE THE TYING IN OF INDIVIDUAL GAS METERS TO THE MAIN. CONTRACTOR IN CONJUNCTION WITH THE GAS COMPANY SHALL DETERMINE THE AMOUNT OF GAS LINE HE IS TO PROVIDE OUTSIDE THE GAS COMPANY'S ALLOWANCE
- 5. REFER TO INTERIOR PLUMBING DRAWINGS FOR TIE-IN OF ALL UTILITIES
- 6. EXISTING UTILITIES SHALL BE VERIFIED IN FIELD PRIOR TO INSTALLATION OF ANY NEW PIPE LINES.
- 7. THRUST BLOCKS SHALL BE LOCATED AT ALL WATER PIPE VALVES, VERTICAL BENDS, AND VERTICAL ELBOWS WITH NFPA BULLETIN NO. 24, SECTION 96, PARAGRAPHS 9605, 9606, AND TABLE 9605
- 8. SANITARY SEWER LINE SHALL BE OF DUCTILE IRON PIPE AT ALL LOCATIONS WHERE SANITARY LINE CROSSES ABOVE OR BELOW A STORM SEWER LINE 9. WHERE WATER PIPING CROSSES THE SANITARY SEWER LINE, THE WATER SERVICE WITHIN TEN FEET OF THE POINT OF CROSSING SHALL BE AT LEAST 12 INCHES ABOVE THE TOP OF THE SEWER LINE. THE SEWER LINE SHALL BE OF DUCTILE IRON WITH MECHANICAL JOINTS AT LEAST 10 FEET ON BOTH SIDES OF THE CROSSING.
- 10. LINES UNDERGROUND SHALL BE INSTALLED, TESTED AND APPROVED BEFORE BACKFILLING.
- 1]. EXISTING DRAINAGE STRUCTURES TO BE INSPECTED AND REPAIRED AS NEEDED AND EXISTING PIPES TO BE CLEANED OUT TO REMOVE ALL SILT AND DEBRIS.
- 12. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY NECESSARY RELOCATION OF EXISTING UTILITIES SUCH AS POWER AND TELEPHONE POLES AND THE COORDINATION OF SUCH WITH THE PROPER UTILITY OWNER

BESTMANAGEMENTPRACTICESNOTES

- 1. CONTRACTOR IS TO ADHERE TO THE CITY OF CARTERSVILLE AND THE STATE OF GEORGIA EROSION AND SEDIMENT CONTROL REGULATIONS
- BEST MANAGEMENT PRACTICES FACILITIES, STORM DRAINAGE FACILITIES AND RETENTION BASINS SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION.
- 3 ALL GRADED AREAS SHALL BE STABILIZED IMMEDIATELY WITH A TEMPORARY FAST GROWING COVER AND/OR MULCH.
- 4. CONTRACTOR SHALL BE RESPONSIBLE DURING CONSTRUCTION FOR THE CONTINUOUS MAINTENANCE OF BEST MANAGEMENT PRACTICES MEASURES AS CALLED FOR ON THE DRAWINGS AND IN THE SPECIFICATIONS
- 5. BEST MANAGEMENT PRACTICES SHALL NOT BE REMOVED UNTIL ALL CONSTRUCTION IS COMPLETE AND UNTIL A PERMANENT GROUND COVER HAS BEEN ESTABLISHED.
- 6. ALL OPEN DRAINAGE SWALES SHALL BE GRASSED AND RIPRAP SHALL BE PLACED AS REOUIRED TO CONTROL EROSION.
- 7. A MINIMUM OF 10 SQUARE YARDS OF 50 POUND STONE SHALL BE PLACED AT ALL DOWNSTREAM HEADWALLS.
- 8. SILT FENCES SHALL BE LOCATED ON SITE TO PREVENT SEDIMENT AND EROSION FROM LEAVING THE PROPERTY LIMITS
- 9. SOILS ENGINEER SHALL CERTIFY THAT ALL FILL AREAS ARE TO A MINIMUM 95 % COMPACTION.
- 10. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE USED AS REQUIRED 11. SILT FENCE SHALL BE CLEANED OR REPLACED WHEN SILT BUILDS UP TO WITHIN 1/2 OF TOP OF SILT
- FENCE.
- 12. MAXIMUM EMBANKMENT SLOPES ARE TO BE AS FOLLOWS: CUT AREAS - 2:1, FILL AREAS - 2:1. 13 DURING AND AFTER CONSTRUCTION, DETENTION PONDS AND DETENTION POND OUTLET
- STRUCTURES SHALL BE CLEANED OF ALL DEBRIS AND EXCESS SEDIMENT. BOTTOM OF PONDS SHALL BE BROUGHT TO ELEVATION AND SHAPE AS SHOWN ON SITE GRADING PLAN.
- 14. SFFDS FOR GRASSED SLOPED AREAS USE BOTH TALL FESCUE GRASS AT 30-40 LBS./AC. AND CLEAN, COMBINE-RUN VIRGATA OR SERICEA LESPEDEZA AT 60-75 LBS./AC.
- 15. ALL CUT AND FILL SLOPES MUST BE SURFACE ROUGHED AND VEGETATED WITHIN SEVEN (7) DAYS OF THEIR CONSTRUCTION.
- 16. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL MEASURES SHALL BE IMPLEMENTED AS NECESSARY THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES, PRIOR TO, OR CONCURRENT WITH, ANY LAND DISTURBING ACTIVITY
- COMMERCIAL/INDUSTRIAL PROJECT NOTES
- . STORM WATER DETENTION FACILITY(IES) SHALL REMAIN IN PLACE AS APPROVED AND AS-BUILT CERTIFIED IN
- PERPETUITY AND SHALL NOT BE ENCROACHED UPON FOR ANY REASON. 2. DETENTION FACILITY(IES) SHALL BE INSPECTED ON A SEMI-ANNUAL BASIS BY OWNER, ANY ACCUMULATED
- TRASH. SEDIMENT, OR DEBRIS SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.
- 3. OWNER/DEVELOPER SHALL ACCEPT FULL LIABILITY FOR THE SAFETY OF ALL PERSONS IN OR AROUND THE 4. OWNER/DEVELOPER SHALL INDEMNIFY CITY AGAINST ALL SUITS BROUGHT ABOUT BY THE EXISTENCE OF
- DETENTION FACILITY(IES) AT ALL TIMES. THE DETENTION FACILITY(IES) 5. OWNER/DEVELOPER SHALL PROVIDE THAT OBLIGATIONS BE TRANSFERRED TO ALL SUCCESSORS AND
- ASSIGNS OF PROPERTY, AND SHALL ACCEPT RESPONSIBILITY FOR INFORMING SUCH SUCCESSORS AND ASSIGNS OF SAID OBLIGATIONS 6. ALL EXISTING AND PROPOSED STORM DRAINAGE FEATURES AFFECTING THIS DEVELOPMENT HAVE BEEN EVALUATED AND/OR DESIGNED IN ACCORDANCE WITH CURRENT REQUIREMENTS AND WILL NOT ADVERSELY

IMPACT ANY PROPOSED ON-SITE IMPROVEMENTS OR UPSTREAM OR DOWNSTREAM PROPERTY.

ADDITIONAL SITE NOTES

- 1. ALL WORK AND MATERIALS SHALL COMPLY WITH THE CITY OF CARTERSVILLE REGULATIONS, CODES AND O.S.H.A. STANDARDS. SITE BOUNDARY AND TOPOGRAPHIC INFORMATION WAS TAKEN FROM A SURVEY BY SMITH AND SMITH LAND SURVEYORS. ALL TOPOGRAPHY, UTILITY LOCATIONS AND ROAD INFORMATION WAS PROVIDED BY SMITH AND SMITH LAND SURVEYORS. STEPHENSON ENGINEERING, INC. ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS INFORMATION
- 3. EXISTING STRUCTURES WITHIN CONSTRUCTION LIMITS ARE TO BE ABANDONED, REMOVED, OR RELOCATED AS NECESSARY.
- 4. CONTRACTOR SHALL OBTAIN ALL PERMITS BEFORE CONSTRUCTION BEGINS
- 5. BUILDING DIMENSIONS SHOWN ON THIS PLAN ARE "LEASE" DIMENSIONS. FOR ACTUAL DIMENSIONS SEE ARCHITECTURAL PLANS.
- 6. SITE CONTRACTOR SHALL FURNISH "AS-BUILT" DRAWINGS INDICATING ALL CHANGES AND DEVIATIONS
- 7. SITE WORK CONTRACTOR IS RESPONSIBLE FOR WORK TO WITHIN 5'-0' OF THE BUILDING.
- 8. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RELOCATION INCLUDING BUT NOT LIMITED TO, ALL UTILITIES, STORM DRAINAGE, SIGNS, TRAFFIC SIGNALS & POLES, ETC., AS REQUIRED FOR CONSTRUCTION.
- 9. ALL WORK SHALL BE IN ACCORDANCE WITH GOVERNING AUTHORITIES SPECIFICATIONS AND SHALL BE APPROVED BY SUCH ALL COST SHALL BE INCLUDED IN BASE BID
- 10. ALL PROPRIETARY DEVICES MUST HAVE MANUFACTURER'S AND ENGINEERS DESIGN SPECIFICATIONS, AND INSTALLATION REQUIREMENTS INCLUDED IN BOTH THE HYDROLOGY STUDY AND PLANS.

GRADING NOTES

1. ALL AREAS TO RECEIVE PAVEMENT, STRUCTURES OR FILL MATERIAL SHALL BE STRIPPED OF ORGANIC MATERIAL, TOPSOIL, AND DEBRIS PRIOR TO CONSTRUCTION.

- 2 ONCE STRIPPING HAS BEEN COMPLETED ALL AREAS TO RECEIVE FILL SHOULD BE PROOF-ROLLED IN THE PRESENCE OF A REPRESENTATIVE OF THE SOILS ENGINEER. SOFT AREAS ENCOUNTERED DURING PROOF-ROLLING SHALL BE STABILIZED BY COMPACTION OR UNDERCUT
- 3. ALL FILL MATERIALS SHOULD BE FREE OF ORGANIC OR OTHERWISE UNSUITABLE MATERIALS, AND COMPACTED TO A MINIMUM DRY DENSITY OF 95%, AS OBTAINED BY STANDARD PROCTOR ASTM D698. FILL SHOULD BE PLACED IN LIFTS NOT TO EXCEED 6 INCHES IN THICKNESS
- 4. ALL UNDERCUT AND FILL OPERATIONS SHOULD BE MONITORED BY A REPRESENTATIVE OF THE SOILS ENGINEER. OWNER, AT HIS OPTION, MAY PERFORM DENSITY TESTS TO VERIFY THAT SPECIFIC COMPACTION IS OBTAINED.
- 5. THE UPPER FOOT OF FILL BENEATH PAVING SHALL BE COMPACTED TO 98% OF MAXIMUM DRY DENSITY PER STANDARD PROCTOR ASTM D698, AT A MOISTURE CONTENT WITHIN 2% TO 3% OF OPTIMUM.
- 6. MAXIMUM CUT OR FILL SLOPES IS 2H:IV 7. IF ACTUAL SITE CONDITIONS VARY FROM ACCEPTED PLANS, IT IS THE OWNER/DEVELOPER'S RESPONSIBILITY TO INFORM THE ENGINEER OF RECORD AND THE CITY ENGINEER FOR ASSESSMENT OF THE CONDITION. PROJECT CONSTRUCTION MAY BE DELAYED DURING ASSESSMENT PERIOD
- 8. ACCEPTANCE OF THESE PLANS DOES NOT CONSTITUTE APPROVAL BY THE CITY OF ANY LAND DISTURBING ACTIVITIES WITHIN WETLAND AREAS. IT IS THE OWNER/DEVELOPER'S RESPONSIBILITY TO CONTACT THE APPROPRIATE REGULATORY AGENCY FOR APPROVAL OF ANY WETLAND AREA DISTURBANCE.
- 9. IT IS THE OWNER/DEVELOPER'S RESPONSIBILITY TO ENSURE THAT THE PROJECT SITE HAS SUFFICIENT GRADE AND ADEQUATE DRAINAGE TO PREVENT FLOODING OF PROPOSED STRUCTURES AND MAINTAIN POSITIVE DRAINAGE THROUGHOUT THE SITE
- 10. DEBRIS FILLS ARE STRICTLY PROHIBITED AT ALL CONSTRUCTION SITES OR WITHIN ANY DEVELOPMENT. ALL WASTE AND CONSTRUCTION DEBRIS SHALL BE PROPERLY DISPOSED OF IN THE LOCAL LANDFILL.
- 11. THE OWNER/DEVELOPER SHALL ACCEPT FULL LIABILITY FOR THE SAFETY OF ALL PERSONS IN OR AROUND THE STORMWATER MANAGEMENT FACILITY AT ALL TIMES.

MATERIALNOTES

- 1. SANITARY SEWER SHALL BE AS INDICATED EITHER PVC, SDR 26 PER ASTM D3034; OR
- DUCTILE IRÓN PIPE PER AWWA C150.
- 2. 6" OR 8" WATER LINE SHALL BE DUCTILE IRON PIPE PER AWWA C151.
- 3. WATER LINES SMALLER THAN 6" SHALL BE EITHER COPPER TUBE TYPE "K" (SOFT) PER ANSI BI6.22 OR PVC, 200 P.S.I., PER ASTM D1784 AND D2241 4. STORM SEWER LINE SHALL BE AS FOLLOWS:
- CMP, FULLY COATED PER ASTM A444 OR ALUMINIZED TYPE II WITH REROLLED ENDS & BANDS. RCP, CLASS III PER AASHTO M170 IN RIGHT-OF-WAY. HDPE (HIGH-DENSITY POLYETHYLENE)
- 5. PRECAST STRUCTURES MAY BE USED AT THE CONTRACTOR'S OPTION.
- 6. ALL CONCRETE TO HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 P.S.L.
- THE GPS LOCATION OF THE CONSTRUCTION EXIT FOR THE SITE. LATITUDE AND LONGITUDE IN DECIMAL DEGREES. N34.1789, W84.7992

- 13. PROVIDE BOLLARDS AT LOCATIONS SHOWN, AND AROUND TRANSFORMERS, GAS

ENGINEER GSWCC# 0000020715

SITE DATA:

FREDDY TEEMS 24 HOUR CONTACT: FREDDY TEEMS **30 AMBERIDGE DRIVE** CARTERSVILLE, GA 30121 PHONE: (770) 382-8166

STEPHENSON ENGINEERING, INC. P.O. BOX 201088 CARTERSVILLE, GEORGIA 30120 PHONE: (770) 382-7877 FAX: (770) 382-3742 SMITH AND SMITH LAND SURVEYORS 2 SOUTH AVENUE CARTERSVILLE, GEORGIA 30120 PHONE: (770) 382-0457 FAX: (770) 387-0543

B.E.I. AERIAL MAPPING 60 EASTBROOK BEND PEACHTREE CITY, GEORGIA 30269 PHONE: (770) 631-1123

0.60 ACRES

0.48 ACRES

IMPERVIOUS AREA = 0.22 AC. = 9,583 SF 0 22 AC./0.60 AC. = 36.67 % OF TOTAL SITE

LIGHT INDUSTRIAL

L-I

THIS TRACT OF LAND DOES NOT LIE WITHIN THE 100 YEAR FLOOD INTERMEDIATE FLOOD ZONE AS PER FEMA COMMUNITY PANEL #13015C0266 G, LAST REVISED SEPTEMBER 28, 2007.

DEVELOPMENT STANDARDS

MINIMUM LOT FRONTAGE MINIMUM FRONT YARD: MINIMUM SIDE YARD: MINIMUM REAR YARD MAXIMUM HEIGHT: PARKING SPACES REQUIRED:

ARKING SPACES PROVIDED

OWNER/DEVELOPER:

TOPOGRAPHIC (SITE)

ENGINEER:

BOUNDARY

SURVEYOR:

(OFFSITE):

SITE AREA:

DISTURBED AREA:

PROPOSED USE


FLOOD NOTE:

ZONING:


IMPERVIOUS SURFACE

TOPOGRAPHIC


110 FEET 20 FEET 15 FEET 20 FEET BUILDINGS SHALL BE NO HIGHER THAN 45 FEET ONE (1) PARKING SPACE FOR EACH ONE THOUSAND (1,000) SQUARE FEET OF GROSS FLOOR AREA. 3,200 SF/1,000 = 3.2 SPACES 4 TOTAL SPACES 1 HANDICAP SPACE & 3 REGULAR SPACES



SHEET INDEX
Boundary Survey
Existing Conditions
Site & Grading Plan
Staking & Utility Plan
Procedures Plan
Initial Erosion Control Plan
Intermediate Erosion Control Plan
Final Erosion Control Plan
Landscape Plan & Details
Pre developed Basin Map
Post developed Basin Map
Site Distance Plan & Profile
Construction Details




P.O. BOX 201088 1130 N. TENNESSEE ST., SUITE D CARTERSVILLE, GEORGIA 30120 AIL: STEPHENSONENG@YAHOO.CO PHONE: (770)382-7877 FAX: (770)382-3742



BOUNDARY SURVEY SHOWN FOR REFERENCE ONLY

REGISTERED LAND	SURVEYOR No. 180
R/W — RIGHT OF WAY IPP → IRON PIN PLACED IPF → IRON PIN FOUND CM → CONCRETE MARKER CH. CHORD L OR A LENGTH OF CURVE	R — RADIUS LP – LIGHT PO - X - X — FENCE







770-382-8166

** SOIL TYPES ONSITE **

AsD - Aragon-Urban land complex, 0 to 15 percent slopes





Utilities Protection Center, Inc.



YOU DIG GEORGIA CALL US FIRST ! 1-800-282-7411 It's The Law !

24 Hr Emergency Contact:

Freddy Teems 770-382-8166

*** ELEVATION NOTE ***

TOPOGRAPHIC INFORMATION PROVIDED BY BARTOW COUNTY GIS. IT IS CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING AND PROPOSED ELEVATIONS AND GRADES ON STREET, STORM DRAINS, AND UTILITIES PRIOR TO CONSTRUCTION. IF AN DISCREPANCY IS FOUND THEN IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE ENGINEER.

*** CAUTION ***

THE UTILITIES SHOWN HEREON ARE FOR THE CONTRACTORS CONVENIENCE ONLY. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THESE PLANS. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS SHOWN AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES WITHIN THE LIMITS OF THE WORK. IF THERE ARE ANY DISCREPANCIES THE ENGINEER MUST BE NOTIFIED ALL DAMAGE MADE TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

*** AS-BUILT NOTE ***

A STORMWATER MANAGEMENT AS-BUILT MUST BE PROVIDED PRIOR TO CERTIFICATE OF OCCUPANCY.

***** CARTERSVILLE FIRE DEPT *** *** REQUIREMENTS ***** Plan Requirements for Cartersville Fire Department

(1) Fire hydrants are to be not more than 500ft. apart with additional hydrants located as necessary to permit all portions of buildings to be reached by hose lays of not more than 300 feet in length. All fire hydrants should be shown on all plans in accordance with Cartersville Development Regulations section 5.3.3. GENERAL COMMERCIAL zoning requires 300 ft. separation.

- (2)All new fire hydrants shall be flow tested in accordance with approved practices of I.S.O, AWWA, and the N.F.P.A to determine the GPM flow for that hydrant. Hydrants will then be color coded in the following fashion in accordance with N.F.P.A 291 and Cartersville ordinance 9-34 Fire Hydrant Testing, Maintenance and Identification:
- a) Barrels: Safety Yellow b) Bonnets and Caps: GPM flow 0 to 499- Safety Red* GPM flow 500 to 999- Safety Orange* GPM flow1000 to 1499- Safety Green
 - GPM flow 1500 +- Safety Blue*
- Trim of bonnet: Silver or White Reflective d) Out of service hydrants shall be solid yellow with no reflective stripe until placed in service or removed

* Color coding is only descriptive of the GPM flow at the time of the last documented test .

- e) All Private hydrants are to be painted solid red, barrels, bonnets, and caps (3) Buildings needing sprinkler systems per Sec.9-29 must have a fire hydrant within 50 ft. of the sprinkler vault and FDC. The vault, FDC, PIV, and the hydrant must be shown on plans. PIV's must be
- electronically supervised and padlocked. (4) Separate sprinkler and fire alarm plans, if required, must also be submitted for approval.
- (5) Fire Department connections shall be located a minimum of 50 ft. or 11/2 times the height of the structure, whichever is greater, from the building.
- (6) In addition to a hard copy, a copy of all CAD files on buildings and subdivisions in DWG, DXF, or CZD format shall be provided. Micro station and AutoCAD have specialized entities that cannot be read into other programs. Within these programs, if the drawing is exploded three times all should be removed. Most, if not all of the drawing, will be read into our FHSketch CAD program. If we could get a floor and plot plan, we can add the other information to our pre-fire plans. Any information that you have will be appreciated. All files should be emailed to <u>MHathaway@cityofcartersville.org</u> or brought on disc, flash drive, or other form of portable media storage device.
- (7) Engineers should follow the latest code editions as adopted by the Georgia Department of Community Affairs O.C.G.A 8-2-20(9)(B). Currently this is 2012 International Fire Code, 2012 NFPA 101 Life Safety Code, and 2010 Edition of ADA, all with State Fire Marshal revisions per the state minimum fire code O.C.G.A 120-3-3. a) All life safety items should be shown on building plans... example; fire extinguishers, emergency lights, exit
- b) Alarm information, if alarm system is required, should be shown on plans. c) Any state fire marshal approved plans must also be submitted to CFD for review <u>after</u> stamped for approval by the state fire marshal office.
- (8) A stamped copy of all applicable plans (site, building, sprinkler, fire alarm, etc.) must be kept on job site at all times (9) Any new building or renovation over 50% will be required to purchase a Knox Box per Sec.9-31. This is an
- emergency key box that is mounted to the building between 6 and 12 feet from the ground. We are not responsible for mounting the box, you are. Order forms can be picked up at Fire Station 1.
- (10) A minimum 20 foot fire lane in accordance with IFC Appendix D should be maintained around all buildings.


*****PARKING-OUTDOOR LIGHTING***** PARKING LOT OUTDOOR LIGHTING SHALL HAVE A MAXIMUM HEIGHT OF FORTY-FIVE (45) FEET AND SHALL BE DIRECTED AWAY AND SHIELDED FROM ABUTTING RESIDENTIAL DISTRICTS.

*****OUTDOOR STORAGE***** IN G-C AND L-I DISTRICTS, OUTDOOR STORAGE MUST BE LOCATED IN A SIDE OR REAR YARD AND SCREENED FROM ALL RIGHTS-OF-WAY, AND RESIDENTIAL DISTRICTS THAT ABUT THE OUTDOOR STORAGE AREA. SUCH STORAGE SHALL BE SCREENED IN ACCORDANCE WITH THE REQUIREMENTS UNDER ZONING ORDINANCE SECTION 4.25.

*****DUMPSTER LOCATION & REQUIREMENTS***** SOLID WASTE CONTAINERS SHALL BE SCREENED FROM ALL STREETS AND ADJOINING PROPERTIES WITH A SOLID, OPAQUE FENCE OR WALL WHICH SHALL BE AT LEAST SIX (6) INCHES TALLER THAN THE CONTAINER.


***** CARTERSVILLE GAS NOTE ***** GAS SERVICE IS NOT BEING AFFECTED AT THIS TIME DURING CONSTRUCTION.

NO GAS SERVICE PROPOSED FOR THIS SITE



1. THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF THE ELECTRICAL SERVICE PRIOR TO CONSTRUCTION (770-387-5631) 2. ANY CUTTING OR TRENCHING OF THE EXISTING CONCRETE OR ASPHALT SHALL BE REPAIRED BY THE CONTRACTOR. CES WILL COMPACT AND BACKFILL THEIR TRENCHES. THE CONTRACTOR SHALL REPAIR OR REPLACE CONCRETE OR ASPHALT SURFACES AS REQUIRED. 3. THE ELECTRICAL CONTRACTOR SHALL REFER TO THE CONTRACTOR'S MANUAL FOR CES CONSTRUCTION SPECIFICATIONS. 4. SERVICE VOLTAGE AND CAPACITY FOR SITE TO BE DETERMINED ONCE A COMPLETED

5. ELECTRICAL SERVICE CONDUIT SHALL BE FURNISHED AND INSTALLED BY CUSTOMER.



TION OF 7 DAYS	ST0 AC	ORAGE BMPN CTIVITIES, TEI	AND CHART OR FOR THE MAJC A'S, CLEARING MPORARY AND BMP'S MUST BE	AND GRUBBI FINAL STABII	NG ACTIVITI LIZATION).	IES, EXCAVA	TION ACTIV	ITIES, UTILIT	TY				A DESCRIPTION C	DF APPROPR NITIAL SEDI	IATE CONTR MENT STORA	OLS AND MEASUI GE REQUIREMEN	RMITTENT STREA OWN ON SHEETS (RES THAT WILL BI NTS AND PERIMET
			Note: Construction sche ACTIV	/ITY	e from date the land d								PHASE I - PERIME	TER CONTI MEDIATE GI	ROL, CONSTR RADING, DRA	UCTION ENTRAN INAGE BMP'S ANI	N ON THE ES&PC I NCE AND SEDIMEN D TEMP. GRASSINC
			COMMENCEMENT OF CONSTR INITIAL EROSION CONTROL BM CLEARING GRUBBING & GRADI INTERMEDIATE EROSION CON GRASSING MAINTAIN SEDIMENT CONTRO INSTALL UNDERGROUND UTILI	AP INTSALLATION ING TROL BMPS L MEASURES									THE INTIAL A INCLUDES TH POND WILL P	ND INTER E INSTAL ROVIDE T TION 751.5	MEDIATE LATION OF HE REQUI 50 (3.5' FRO	EROSION & SI F A PERMANEN RED SEDIMEN	PHASE TO THE EDIMENTATIO NT DETENTION IT STORAGE. T OND ELEVATIC
VORK D.			INSTALL PAVING BUILDING CONSTRUCTION FINAL LANDSCAPING FINAL PHASE OF ERO. AND SED. COMPLETION OF CONSTRUCTIV										ALL TEMPORA PERMANENT	ARY MEAS GRASSING	SURES AFT G. THE WA	ER DISTURBE TER QUALITY	ION CONTROL D AREAS HAVE I DEVICE WILL AS BEEN FULLY
) O _PROV	/IDE COMPLE	TE REQUIREM	ENTS OF INSP	PECTIONS AN	ND RECORD	KEEPING BY	PRIMARY PE	ERMITTEE.			000	GRAPHIC SCALE ALL SCALES AND	NORTH AR	ROWS ARE PI		
	4. INSP A. PERI (1). EAC PRIMA SPILLS	PECTIONS. MITTEE REQUIR CH DAY WHEN A RY PERMITTEE AND LEAKS FRO	EMENTS. ANY TYPE OF CONS SHALL INSPECT: (/ DM VEHICLES AND	STRUCTION ACT A) ALL AREAS AT EQUIPMENT AN	IVITY HAS TAKI THE PRIMARY D (B) ALL LOC <i>I</i>	EN PLACE AT A PERMITTEE'S S ATIONS AT THE	A PRIMARY PER SITE WHERE PE E PRIMARY PER	MITTEE'S SITE, (TROLEUM PRO MITTEE'S SITE V	CERTIFIED PERS DUCTS ARE STO WHERE VEHICLE	DRED, USED, OR HA ES ENTER OR EXIT	ANDLED FOR	37.	THE FOLLOWING PLANS INCLUDE INTERMEDIATE A WITH THE CORR	G: AN EXISTIN AND FINAL I RECT INTER	NG SITE PLAN PHASE SHEET VALS OVERLA	SHEET WITH CO S OF THE PLAN SI AYING THE ORIGI	UR LINES DRAWN DNTOURS AT CORF HOW THE PROPOS INAL CONTOUR LI RS FOR INFRASTRI
	(2). ME A NOTI	EASURE RAINFA ICE OF TERMIN	E SEDIMENT TRAC LL ONCE EVERY 2- ATION IS SUBMITT	HOURS EXCEPT	ANY NON-WO	RKING SATUR	DAY, NON-WOI	RKING SUNDAY	AND NON-WOR	RKING FEDERAL H		38.	CRITERIA FROM	ATIVE BMP'S	6 WHOSE PER	FORMANCE HAS	BEEN DOCUMENT DFESSIONAL (UNLE
	A CRO (3). CEI	RTIFIED PERSON	EGETATION AND A NEL (PROVIDED F THE END OF A STO	BY THE PRIMARY	PERMITTEE) SI	HALL INSPECT	THE FOLLOWI	NG AT LEAST OI	NCE EVERY SEVE	EN (7) CALENDAR	DAYS AND		SOIL AND WATER	R CONSERV. HASES OF T	ATION COMN HE PLAN ARE	AISSION): CONSISTENT WI	TH THE MANUAL
	NON-V SATUR BUSINI	VORKING RDAY, NON-WOI ESS DAY AND/OI	THE END OF A STO RKING SUNDAY OF R WORKING DAY, '	ANY NON-WOR	KING FEDERAI	L HOLIDAY IN V	VHICH CASE TI	HE INSPECTION	SHALL BE COMI	PLETED BY THE EN	ND OF THE NEXT		SHOWN IN THRE	EE PHASES V	VITH EACH P	HASE SHOWN ON	EGEND FROM THE NA SEPARATE SHE
	CONTF CORRE	RY PERMITTEE ROL MEASURES ECTLY. WHERE	FOR STORAGE OF IDENTIFIED IN TH	E PLAN APPLICA	BLE TO THE PRI	IMARY PERMIT	TTEE'S SITE SHA	LL BE OBSERVE	D TO ENSURE TH	HAT THEY ARE OP	ERATING	39.					UIVALENT BMP LIS SIA 2016 EDITION. N
EAM	PREVE ANNUA	NTING SIGNIFIC AL VEGETATION	NS OR POINTS ARE CANT IMPACTS TO J AND A SEEDING (E CONDUCTED UN	RECEIVING WA	TER(S). FOR AR NNIALS APPRC	REAS OF A SITE	THAT HAVE UN HE REGION, TH	NDERGONE FIN.	AL STABILIZATIO	ON OR ESTABLISH	ED A CROP OF	40.	DELINEATION OF DESIGNATED TR	F 25-FOOT U OUT STREA	NDISTURBED MS. CLEARLY	D BUFFERS OF STA Y NOTE AND DELI	ATE WATERS AND INEATE ALL AREAS
ANY PERMIT. E AREAS	NOTIC VEGET FOR, PO SHALL ENSUR	E OF TERMINAT TATION AND A S OLLUTANTS EN BE OBSERVED T RE THAT THEY A	RE OPERATING CO	BY EPD) THE ARE ET PERENNIALS A NAGE SYSTEM A DRRECTLY. WHE	AS OF THE SITI PPROPRIATE F ND THE RECEIV RE DISCHARGE	E THAT HAVE U FOR THE REGIC VING WATER (S E LOCATIONS C	JNDERGONE FI DN. THESE AREA S). EROSION AN DR POINTS ARE	NAL STABILIZA AS SHALL BE INS D SEDIMENT CO ACCESSIBLE, TH	TION OR ESTABI SPECTED FOR EV ONTROL MEASU HEY SHALL BE IN	LISHED A CROP OF TIDENCE OF, OR TH RES IDENTIFIED IN	F ANNUAL HE POTENTIAL N THE PLAN		THERE ARE N				5 NOTE *** ed within 200 fe
GTREAM DI, THE	(5). BAS EROSIO	SED ON THE RES ON, SEDIMENTA	CONTROL MEASUR GULTS OF EACH IN TION AND POLLUT	SPECTION, THE S FION CONTROL F	TTE DESCRIPTI PLAN, THE PLAN	ON AND THE P N SHALL BE RE	OLLUTION PRE VISED AS APPRC	EVENTION AND OPRIATE NOT LA	CONTROL MEAS	EN (7) CALENDAR	DAYS	41.	SITE:				ATERS LOCATED C
IN THE	DAYS F (6). A R	FOLLOWING EA	H INSPECTION TH	AT INCLUDES TH	E NAME(S) OF (CERTIFIED PER	RSONNEL MAKI	NG EACH INSPI	ECTION, THE DA	ATE(S) OF EACH IN	ISPECTION,		ALL STATE WAT	THE PLAN.			00 FEET OF THE PF
	AND PO READII HAS UI SECON	OLLUTION CON LY AVAILABLE A NDERGONE FIN ID BUSINESS DA	EE (IE., INITIAL, INT TROL PLAN, AND T A DESIGNATED AL STABILIZATION Y AND/OR WORKI	ACTIONS TAKEN ALTERNATE LOC NAND A NOTICE NG DAY AND SHA	IN ACCORDAN ATION UNTIL T OF TERMINATI ALL IDENTIFY A	CE WITH PART THE ENTIRE SIT ON IS SUBMITT LL INCIDENTS	I IV.D.4.a(5). OF IE OR THAT PO IED TO EPD. SU OF BEST MANA	THE PERMIT SF RTION OF CONS CH REPORTS SF GEMENT PRAC	HALL BE MADE A STRUCTION PRO HALL BE READILY TICES THAT HAV	ND RETAINED AT DJECT THAT HAS B Y AVAILABLE BY EI VE NOT BEEN PRO	THE SITE OR BE BEEN PHASED ND OF THE PERLY		THERE ARE NO				ED WITHIN 200 FE
	A CERT REPOR	TIFICATION THA T SHALL BE SIG	AINTAINED AS DE AT THE BEST MAN. NED IN ACCORDA ETE REQUIREM	AGEMENT PRACT	FICES ARE IN C V.G.2. OF THIS F	OMPLIANCE W PERMIT.	/ITH THE EROS	ION, SEDIMENT	ATION AND POL	LUTION CONTRO		42.				IBUTING DRAINA IN POND IS SHOW	AGE BASINS ON TH VN ON SHEET C7.
	SAMI 1) TH BELC RECH	PLING FREQU IE PRIMARY I OW. FOR A QU EIVING WATI	JENCY PERMITTEE MU UALIFYING EVI ER AND/OR FRO	JST SAMPLE II ENT, THE PER OM A MONITC	N ACCORDA MITTEE SHA ØRED OUTFA	NCE WITH T LL SAMPLE LL LOCATIO	THE PLAN AT AT THE BEGI DN WITHIN F	T LEAST ONC NING OF AN ORTY-FIVE	CE FOR EACH NY STORM WA (45) MINUTE	RAINFALL EVE ATER DISCHAR ES OR AS SOON			CONDITIONS: SEPARATE HY	YDROLOG	Y STUDY A	ATTACHED. PF	ASINS FOR BOTH T RE DEVELOPED IEETS C6 & C7.
	PERM	MITTEE'S COI ER THE BEGII	NNING OF THE	ERMITTEE SHA STORM WATI	ALL TAKE SA ER DISCHAR	MPLES AS SO GE.	OON AS POSS	SIBLE, BUT IN			ELVE (12) HOURS	44.	AN ESTIMATE OF				RGE FLOW OF TH
	REAC THIS	(A) FOR EA CHES OR EXC 5 PERMIT AFT RATIONS, IN	EEDS 0.5 INCH ER ALL CLEAR THE DRAINAGE	HE SITE THAT WITH A STOR ING AND GRU AREA OF THI	DISCHARGE .M WATER D JBBING OPEI E LOCATION	S TO A RECE DISCHARGE RATIONS HA	EIVING WAT THAT OCCU AVE BEEN CC AS THE SAME	ER OR FROM RS DURING MPLETED, B PLING LOCA	NORMAL BU UT PRIOR TO TION.	SINESS HOURS COMPLETION	RAIN EVENT THA' S AS DEFINED IN I OF MASS GRADII		*** ES	TIMAT	EXIS	J NOFF C TING CN = 5 OSED CN = 7	
	BUSI OPEF	FÌRST RAIN I NESS HOURS	EVENT THẤT R AS DEFINED IN	EACHES OR E	XCEEDS 0.5 I Feither 90 I	INCH WITH DAYS AFTER	A STORM W. THE FIRST S	ATER DISCH SAMPLING E	ARGE THAT (VENT OR AF	OCCURS DURI TER ALL MASS		45.	STORM-DRAIN PI DISCHARGES WI			ES WITH APPROP	RIATE OUTLET PR
	TO A Shai	(C) AT THE RECEIVING LL BE DEFINE	WATER OR FRO D AND IMPLEN	OM AN OUTFA 1ENTED WITH	ALL ARE NOT HIN TWO (2)	F PROPERLÝ BUSINESS F	DESIĜŃED, I DAYS, AND TU	NSTALLED A	AND MAINTAI MPLES SHALI	INED, CORREC L BE TAKEN FR	OM DISCHARGES				1		PROTECTION
	HOU	URS* UNTIL T PROPERLY D	HE SELECTED 1 ESIGNED, INST	TURBIDITY STA ALLED AND M	ANDARD IS A AINTAINED;	ATTAINED, C	OR UNTIL PO	ST-STORM E	VENT INSPEC	CTIONS DETER	RMAL BUSINESS MINE THAT BMPS CAUSE THERE WA		ST (STRUCTURE)		WIDTH (FT)	Width (Wl)(FT)	Downstream (W2) (FT)
	REPO	DISCHARGE), DRT OF WHY SEQUENT SAM	THE PERMITTE SAMPLING WA APLING OBLIGA	EE, IN ACCORI AS NOT PERFO ATIONS UNDE	DANCE WITH RMED. PROV R (A), (B) OR	H PART IV.D. VIDING THIS & (C) ABOVE;	4(6), MUST I 5 JUSTIFICAT AND	NCLUDE A V TON DOES N	VRITER JUST	TFICATION IN THE PERMITTI	THE INSPECTION EE OF ANY		SPILLWAY FLUME "A"	10 10	10.0 5.0	10.0 15.0	20.0
GES:	ACTI	T HÁVE MET IVITIES THAT		G REQUIRED H HE SAMPLING	BY (a) ABOVE	E SHALL SAN	IPLE IN ACCO	ORDANCE W	/ITH (b). THO	SE EXISTING C	TE OF THIS PERMI CONSTRUCTION JAL SAMPLING	1,	46. SOIL SERIE THE HIGH	ES AND THEI EST LEVEL (R DELINEATI DF SOIL SURV	ON: 'EY REQUIRED FO	OR THE PROJECT S
REAS G.	*NOT FROI	TE THAT THE M ANY RAIN	E PERMITTEE N EVENT THAT R	IAY CHOOSE T REACHES OR E	TO MEET THE XCEEDS 0.5 1	E REQUIREN INCH AND A	MENTS OF (a) ALLOWS FOR) AND (b) AB SAMPLING	OVE BY COLL AT ANY TIME	ECTING TURB	IDITY SAMPLES DR WEEK.		SURVEY FO DELINEAT	OR PROJECT	IS THAT WILL D IS SHOWN (DN THE PROJI	L BE USING SEPTI ON THE EXISTINC ECT SITE IS SHOV	IC SYSTEMS, MUST 5 SITE PLAN AND/C VN ON THE SHEET
ND 3	THE P	RIMARY PER	TE DETAILS FOI MITTEE SHALL ESIGNATED AL	RETAIN THE	FOLLOWING	G RECORDS A	AT THE CON	STRUCTION	SITE OR THE		ALL BE READILY S A NOT IS		AsD -	Arago			RE LISTED BI mplex, 0 to
ER, G	SUBM a. A CC b. A CC	ITTED IN ACC OPY OF ALL N OPY OF THE H	CORDANCE WI OTICES OF INT EROSION, SEDIN	TH PART VI: FENT SUBMIT MENTATION A	TED TO EPD: ND POLLUT	ION CONTR	OL PLAN RE	QUIRED BY I	THIS PERMIT;	;			47. LIMITS (OF DISTURB	ANCE FOR EA	ACH PHASE OF CO	DNSTRUCTION: PHASE DELINEATE
POSAL ED BY	d. A C0 e. A C0	OPY OF ALL N OPY OF ALL IN	IONITORING II NSPECTION REI	NFORMATION PORTS GENER	I, RESULTS, A ATED IN AC	AND REPORT CORDANCE	IS REQUIREI WITH PART) BY THIS PE IV.D.4.a. OF	RMIT; THIS PERMIT	-	T IV.A5. OF THIS P T III.D.2. OF THIS I		THE INS	TALLATION ATES THE EI	NOF PERIMET	TER CONTROL AN FO BE DISTURBEI	PHASE DELINEATE ND INITIAL SEDIMI D FOR THAT PHAS . AREAS TO BE DIST
M AND TIONS	2. COP	PIES OF ALL N		ENT, NOTICE	S OF TERMIN	NATION, REF	PORTS, PLAN	S, MONITOR			NG INFORMATION INUOUS MONITO		DRAINA	GE LOCATIO	DN. SEDIMEN	T STORAGE VOLU	STORAGE PER ACI EXCAVATED INLE JME MUST BE IN P
	INSTR INTEN EITHE	RUMENTATIC NT TO BE COV ER PRODUCE	N, EROSION , S VERED BY THIS D OR USED IT F	EDIMENTATIO PERMIT AND FOR A PERIOD	ON AND POL ALL OTHER OF AT LEAS	LUTION COI RECORDS R T THREE YE	NTROL PLAN EQUIRED BY ARS FROM T	IS, RECORDS THIS PERMI HE DATE TH	G OF ALL DATA IT SHALL BE F AT THE NOT	A USED TO CO RETAINED BY T IS SUBMITTEI	MPLETE THE NOT THE PERMITTEE W D IN ACCORDANC	TICE OF /HO E WITH	DECISIO	N NOT TO U	JSE A SEDIME		E SITE HAS BEEN AG BE INCLUDED IN T PROVIDED.
RGIA. 3	ALTEF REQU	RNATIVE LOC EST OF THE I		THE CONSTRU ME UPON WR	JCTION ACT ITTEN NOTII	FIVITY HAS C FICATION TO	CEASED AT T O THE PERMI	THE PERMITT ITTEE.	FED SITE. THI	IS PERIOD MAY	R AT A DESIGNATI (BE EXTENDED BY		SEDIME				AGE REQUIR
SPOSED DURES.	ACCC APPRO	ORDANCE WI OVED); THE (TH METHODO GUIDANCE DOG	LOGY AND TE CUMENT TITL	ST PROCEDU .ED "NPDES S	URES ESTAB	LISHED BY 40	CFR PART I	136 (UNLESS C	OTHER TEST PF	E CONDUCTED IN ROCEDURES HAVI 2-001" AND GUIDA	E BEEN	SEDIVIE				DESIGN CALC
GES:	1. 2.	SAMPLE CON SAMPLES SH	T MAY BE PREE NTAINERS SHC OULD BE WELI TH, WELL CLE	OULD BE LABEI L MIXED BEFO	LED PRIOR T RE TRANSFE	ERRING TO A	A SECONDAR	Y CONTAIN		TING SAMPLE	S. THE JARS			VOLUN	0.60 ACRE	S ED = 67 CY/AC	REX 0.40 ACRI
ND D	4.	MANUAL, AU IMMEDIATE	LY, BUT IN NO (RISING STAG CASE LATER T	E SAMPLING HAN 48 HOU	G MAY BE UT JRS AFTER C	TILIZED. SAM COLLECTION	. HOWEVER	, SAMPLES FR	ROM AUTOMA	LD BE ANALYZED TIC SAMPLERS M			VOLUN	AE PRÔVID	ED = 100.7 CY =	2,719 CF
ER, G		UTILIZED. IF	FAUTOMATIC S TEE MUST UT	SAMPLING IS U ILIZE MANUA	JTILIZED AN L SAMPLING	ND THE AUT G OR RISING	OMATIC SAN STAGE SAM	APLER IS NO PLING DURI	T ACTIVATEI NG THE NEXT	D DURING THE T QUALIFYING	AUTOMATED ANA E QUALIFYING EV E EVENT. DILUTION IETER. SAMPLES A	ENT, N					
S	5.	NOT REQUII SAMPLING A BE REPORTE	RED TO BE COC NALYSIS OF TH D TO EPD AS SI	DLED. HE RECEIVING PECIFIED IN PA	WATER(S) ART IV.E.	OR OUTFAL	LS BEYOND 7				THIS PERMIT MU						
A ND	3. Appel		SURFAC	ATER (SUPPO DE WATER DRA	RTING WAR AINAGE ARE	M WATER F A, SQUARE N	ISHERIES) MILES										
	1.00-10	0-4.99	5-0.50+/-	10-24.99 200	25-40.50+/- 400	50-90.50+ 750	·/- 100-240.5 750	0+/- 250-490. <u>5</u> 750	50+/ <u>500+</u> 750								
ED	10.01-25 25.01-50	50 50	100 50	100 100	200 100	300 200	500 300	750 750	750 750								
6.	50.01-100 100.01+	50	50	50	100	100	150	300	600								
AT.		50 TO USE THE	50 SE TABLES, SEL	50 ECT THE SIZE	50 F (ACRES) OF	50 F THF FACIL	100 ITY OR COM	200 MON DEVEL	100 Opment								

THEN, SELECT THE SURFACE WATER DRAINAGE AREA (SQUARE MILES).

STREAMS AND OTHER WATER BODIES INTO WHICH IEETS C4.2-C.4.4.

VILL BE IMPLEMENTED AT THE CONSTRUCTION SITE RIMETER CONTROL BMP'S, (2) INTERMEDIATE GRADING

S&PC PHASED EROSION CONTROL PLANS: DIMENT STORAGE

THE INTERMEDIATE PHASE OF PROJECT ATION CONTROL PLAN FOR THIS PROJECT JTION POND. THE PERMANENT DETENTION GE. THERE IS NO STORMWATER RELEASE ATION 748.00), WHICH IS THE OVERFLOW

FROL PLAN WILL INCLUDE THE REMOVAL OF HAVE BEEN FULLY STABILIZED WITH WILL BE INSTALLED ON THE DETENTION FULLY STABILIZED.

RAWN AT AN INTERVAL IN ACCORDANCE WITH

CORRECT INTERVALS. THE INITIAL, PROPOSED GRADES IN BOLD CONTOUR LINES OUR LINES. ELEVATIONS OF BOTH THE EXISTING ASTRUCTURE PROJECTS ARE SHOWN USING

- JMENTED TO BE EQUIVALENT TO OR SUPERIOR (UNLESS DISAPPROVED BY EPD OR THE GEORGIA
- ANUAL AND SHOW UNIFORM CODING SYMBOLS OM THE MANUAL IS INCLUDED. THE PLANS ARE FF SHFFT
- BMP LIST. PLEASE REFER TO APPENDIX A-2 OF THE TION. N/A
- S AND 50-FOOT UNDISTURBED BUFFERS ALONG AREAS OF IMPACT:

200 FEET OF THIS SITE.

ATED ON AND WITHIN 200 FEET OF THE PROJECT THE PROJECT SITE HAVE BEEN DELINEATED ON

200 FEET OF THIS SITE.

ON THE PROJECT SITE:

BOTH THE PRE- AND POST-DEVELOPED OPED AND POST DEVELOPED DRAINAGE

OF THE SITE PRIOR TO AND AFTER



LET PROTECTION TO ACCOMMODATE

TION (St) TABLE										
tream Width	Avg. Stone Dia.	Stone Depth	Q(2YR)	Velocity	Q(25YR)	Velocity				
V2) (FT)	(d50) (FT)	(D) (FT)	(cfs)	(fps)	(cfs)	(fps)				
20.0	0.5	1.13	NONE	N/A	0.08	0.64				
20.0	0.5	1.13	0.60	1.83	0.87	2.12				

JECT SITE, SUCH AS A LEVEL THREE OR LEVEL FOUR , MUST BE DELINEATED ON THE PLAN. THE SOIL SERIES AND/OR THE INITIAL PHASE PLAN. A CHART LISTING SHEET WITH THEIR DELINEATION.

ED BELOW:

, 0 to 15 percent slopes

NEATES ONLY THE AREA REQUIRED TO BE DISTURBED FOR SEDIMENT STORAGE. THE INTERMEDIATE PHASE PHASE, SUCH AS GRADING, DRAINAGE, UTILITIES, ETC. BE DISTURBED SUCH AS INDIVIDUAL LTS, ETC

PER ACRE DRAINED USING A TEMPORARY SEDIMENT D INLET SEDIMENT TRAPS FOR EACH COMMON

BE IN PLACE PRIOR TO AND DURING LAND DISTURBANCE EEN ACHIEVED. A WRITTEN RATIONALE EXPLAINING THE ED IN THE PLAN FOR EACH COMMON DRAINAGE

QUIRED & PROVIDED

THIN THE PERMANENT DETENTION POND

ULATIONS TABLE	
ES = 27 CY = 729 CF	


49. LOCATION OF BEST MANAGEMENT PRACTICES THAT ARE CONSISTENT WITH AND NO ESS STRINGENT THAN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.USE UNIFORM CODING AND SYMBOLS FROM THE MANUAL: BMP'S FOR THE PLAN ARE CONSISTENT WITH THE MANUAL AND SHOW UNIFORM CODING SYMBOLS FROM THE MANUAL. THE UNIFORM CODING SYMBOLS LEGEND FROM THE MANUAL IS INCLUDED. A THREE PHASE EROSION CONTROL PLAN IS NOT REQUIRED FOR THIS LOT DUE TO THE MINIMUM AMOUNT OF DISTURBED AREA. EROSION CONTROL MEASURES FOR TEMPORARY GRASSING AND DUST CONTROL ARE SHOWN ON THIS PLAN, ALONG WITH SILT FENCE AND A CONSTRUCTION ENTRANCE WHICH WILL BE IMPLEMENTED AND MAINTAINED UNTIL PERMANENT GRASSING IS IMPLEMENTED.

- **50.** PROVIDE DETAILED DRAWINGS FOR ALL STRUCTURAL PRACTICES. SPECIFICATIONS MUST, AT A MINIMUM, MEET THE GUIDELINES SET FORTH IN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. SEE DETAIL SHEETS FOR ALL EROSION & STRUCTURAL DETAILS.
- **51.** PROVIDE VEGETATIVE PLAN, NOTING ALL TEMPORARY AND PERMANENT VEGETATIVE PRACTICES. INCLUDE SPECIES. PLANTING DATES AND SEEDING. FERTILIZER, LIME AND MULCHING RATES. VEGETATIVE PLAN SHALL BE SITE SPECIFIC AND APPROPRIATE OF YEAR OF THAT SEEDING WILL TAKE PLACE AND FOR THE APPROPRIATE GEOGRAPHIC REGION OF GEORGIA. SEE DETAIL SHEETS

	*** TEMPORARY***
	BMP'SNOTE
ALL TEMP	PORARY BMP'S ARE TO BE REMOVED PRIOR TO
	FILING A N.O.T.
	(NOTICE OF TERMINATION)
ALSO, CH	ERTAIN TEMPORARY BMP'S WILL REMAIN IN
PLACE UN	NTIL ALL REQUIREMENTS HAVE BEEN MET TO
FII	LE FOR THE NOTICE OF TERMINATION.

BEST MANAGEMENT PRACTICES TO MINIMIZE OFF-SITE TRACKING OF SEDIMENTS AND THE GENERATION OF DUST:

FFSITE VEHICLE TRACKING STABILIZED CONSTRUCTION EXIT HAS BEEN PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENT. SEE INITIAL AND INTERMEDIATE EROSION CONTROL SHEETS FOR CONSTRUCTION EXIT LOCATION AND SEE DETAIL SHEET FOR SPECIFIC DETAILS. THE PAVED STREET ADJACENT TO THE SITE EXIT WILL BE INSPECTED DAILY FOR TRACKING OF MUD, DIRT OR ROCK. DUMP TRUCKS HAULING MATERIAL FROM THE CONSTRUCTION SITE WILL BE COVERED WITH A TARPOULIN.




WATER TRUCKS TO BE USED WHEN NECESSARY FOR DUST CONTROL


CERTIFICATION AND SIGNATURE IN ACCORDANCE WITH SECTION V.G.2.d. OF THE PERMIT: "I CERTIFY UNDER THE PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONAL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED UPON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE **FVIOLATIONS**

POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING V
OWNER/DEVELOPER

V 7.1			
velocity			
Velocity (fps)			
0.64			



SHEET NO.



Utilities Protection Center, Inc.

YOU DIG GEORGIA CALL US FIRST ! 1-800-282-7411 It's The Law !

24 Hr Emergency Contact:

Freddy Teems 770-382-8166

***** MAINTENANCE STATEMENT ***** EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL

IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIEMENT SOURCE. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION.

***** ELEVATION NOTE *****

TOPOGRAPHIC INFORMATION IS BASED ON A FIELD RUN TOPOGRAPHIC MAP PROVIDED BY SMITH AND SMITH LAND SURVEYORS AND AERIAL TOPOGRAPHY. IT IS CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING AND PROPOSED ELEVATIONS AND GRADES ON STREET, STORM DRAINS, AND UTILITIES PRIOR TO CONSTRUCTION. IF AN DISCREPANCY IS FOUND THEN IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE ENGINEER.

*** CAUTION ***

THE UTILITIES SHOWN HEREON ARE FOR THE CONTRACTORS CONVENIENCE ONLY. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THESE PLANS. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS SHOWN AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES WITHIN THE LIMITS OF THE WORK. IF THERE ARE ANY DISCREPANCIES THE ENGINEER MUST BE NOTIFIED. ALL DAMAGE MADE TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

***** STABILIZATION STATEMENT ***** ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

***** CLEARING STATEMENT ***** MINIMIZE CLEARING TO THAT AMOUNT OF LAND MINIMALLY NECESSARY FOR THE FOOTPRINT OF THE STRUCTURE, RIGHT-OF-WAY, REQUIRED DRAINAGE OR REQUIRED PARKING.

***** ESTIMATED RUNOFF COEFFICIENT ***** EXISTING CN = 55 PROPOSED CN = 73

*** BUFFER ACTIVITY STATEMENT *** ACTIVITIES SHALL BE CONDUCTED WITHIN THE 25 FOOT STREAM BUFFER ALONG THE BANKS OF ALL STATE WATERS.

***** SEDIMENT STATEMENT ***** THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR

CONCURRENT WITH, LAND-DISTURBING ACTIVITIES.

EROSION CONTROL NOTES

- 1. EROSION CONTROL MEASURES WILL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RAIN, AND REPAIRED BY GENERAL CONTRACTOR.
- 2. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE
- INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION. B. ALL EROSION CONTROL STANDARD DETAILS, INCLUDING GA. EROSION
- AND SEDIMENT CONTROL PRACTICES ARE SHOWN ON DETAIL SHEETS. 4. THIS SHEET FOR EROSION AND SEDIMENT CONTROL PURPOSES ONLY.
- 5. MAINTAIN SILT FENCE AT TOE OF LONG CUT SLOPES AT EDGE

OF RIGHT-OF-WAY UNTIL STABILIZATION.

***** EROSION CONTROL ***** EROSION CONTROL MEASURES WILL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RAIN, AND REPAIRED BY GENERAL CONTRACTOR.


***** EROSION AMENDMENT NOTE *****


AMENDMENTS TO THE ES & PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

> *** TYPICAL LOT PLAN *** THERE IS NO TYPICAL LOT FOR THIS PROJECT. THE WHOLE SITE IS THE ONLY LOT LOCATED ON SITE.

ENGINEER GSWCC# 0000020715

CONSTRUCTION	ON SO	CHED	ULE				
Note: Construction schedule is a general timeline from date the land disturbance permit is issued.							
ACTIVITY	Month 1	Month 2	Month 3	Month 4	Month 5	Month 6	
COMMENCEMENT OF CONSTRUCTION	1						
INITIAL EROSION CONTROL BMP INTSALLATION							
CLEARING GRUBBING & GRADING							
INTERMEDIATE EROSION CONTROL BMP'S							
GRASSING			2				
MAINTAIN SEDIMENT CONTROL MEASURES							
INSTALL UNDERGROUND UTILITIES							
INSTALL PAVING							
BUILDING CONSTRUCTION							
FINAL LANDSCAPING							
FINAL PHASE OF ERO. AND SED. CONTROL PLAN							
COMPLETION OF CONSTRUCTION							





Utilities Protection Center, Inc.

YOU DIG GEORGIA CALL US FIRST ! 1-800-282-7411 It's The Law !

24 Hr Emergency Contact:

Freddy Teems 770-382-8166

***** MAINTENANCE STATEMENT ***** EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE EFFECTIVE EROSION

CONTROL, ADDITIONAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIEMENT SOURCE. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION.

***** ELEVATION NOTE *****

TOPOGRAPHIC INFORMATION IS BASED ON A FIELD RUN TOPOGRAPHIC MAP PROVIDED BY SMITH AND SMITH LAND SURVEYORS AND AERIAL TOPOGRAPHY. IT IS CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING AND PROPOSED ELEVATIONS AND GRADES ON STREET, STORM DRAINS, AND UTILITIES PRIOR TO CONSTRUCTION. IF AN DISCREPANCY IS FOUND THEN IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE ENGINEER.

*** CAUTION ***

THE UTILITIES SHOWN HEREON ARE FOR THE CONTRACTORS CONVENIENCE ONLY. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THESE PLANS. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS SHOWN AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES WITHIN THE LIMITS OF THE WORK. IF THERE ARE ANY DISCREPANCIES THE ENGINEER MUST BE NOTIFIED. ALL DAMAGE MADE TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

***** STABILIZATION STATEMENT ***** ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

***** CLEARING STATEMENT ***** MINIMIZE CLEARING TO THAT AMOUNT OF LAND MINIMALLY NECESSARY FOR THE FOOTPRINT OF THE STRUCTURE, RIGHT-OF-WAY, REQUIRED DRAINAGE OR REQUIRED PARKING.

***** ESTIMATED RUNOFF COEFFICIENT ***** EXISTING CN = 55 PROPOSED CN = 73

*** BUFFER ACTIVITY STATEMENT *** ACTIVITIES SHALL BE CONDUCTED WITHIN THE 25 FOOT STREAM BUFFER ALONG THE BANKS OF ALL STATE WATERS.

***** SEDIMENT STATEMENT ***** THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND-DISTURBING ACTIVITIES.

EROSION CONTROL NOTES

- 1. EROSION CONTROL MEASURES WILL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RAIN, AND REPAIRED BY GENERAL CONTRACTOR.
- 2. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE
- INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION. B. ALL EROSION CONTROL STANDARD DETAILS, INCLUDING GA. EROSION
- AND SEDIMENT CONTROL PRACTICES ARE SHOWN ON DETAIL SHEETS. 4. THIS SHEET FOR EROSION AND SEDIMENT CONTROL PURPOSES ONLY.
- 5. MAINTAIN SILT FENCE AT TOE OF LONG CUT SLOPES AT EDGE OF RIGHT-OF-WAY UNTIL STABILIZATION.

***** EROSION CONTROL ***** EROSION CONTROL MEASURES WILL BE INSPECTED AT LEAST WEEKLY AND AFTER


EACH RAIN, AND REPAIRED BY GENERAL CONTRACTOR.


***** EROSION AMENDMENT NOTE ***** AMENDMENTS TO THE ES & PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.


> *** TYPICAL LOT PLAN *** THERE IS NO TYPICAL LOT FOR THIS PROJECT. THE WHOLE SITE IS THE ONLY LOT LOCATED ON SITE.


ENGINEER GSWCC# 0000020715

CONSTRUCTION SCHEDULE						
Note: Construction schedule is a general timeline from date the land disturbance permit is issued.						
ACTIVITY	Month I	Month 2	Month 3	Month 4	Month 5	Month 6
COMMENCEMENT OF CONSTRUCTION	I					
INITIAL EROSION CONTROL BMP INTSALLATION						
CLEARING GRUBBING & GRADING						
INTERMEDIATE EROSION CONTROL BMP'S						
GRASSING						
MAINTAIN SEDIMENT CONTROL MEASURES						
INSTALL UNDERGROUND UTILITIES						
INSTALL PAVING						
BUILDING CONSTRUCTION						
FINAL LANDSCAPING						
FINAL PHASE OF ERO. AND SED. CONTROL PLAN						
COMPLETION OF CONSTRUCTION						











Growth	6	Remarks
rate	Group	Kemarks
Medium	Deciduous	Flowers fragrant, pinkish-white
Slow	Deciduous	Specimen or masses
Slow to Medium	Deciduous	White flowers
Medium	Broadleaved evergreen	Dark green foliage specimen; screening
Fast	Broadleaved evergreen	Screening, hedge
low	Semi-evergreen	White flowers
ast	Deciduous	White, pink, or red flowers
ledium	Deciduous	Spring flowering
edium	Deciduous	White flowers
ledium	Deciduous	Red fall color

Sec. 17-74 Large	1	1	T	1	1	
Common name (Botanical name)	Texture	Form	Height/ Spread	Growth rate	Group	Remarks
Ash, white (fraxinus americana)	Fine to medium	Spreading	6070'/ 3040'	Fast	Deciduous	Shade
Beech, american (fagus grandifolia)	Coarse	Rounded	6080'/ 3545'	Medium to fast	Deciduous	Shade
Birch, river (betula nigra)	Medium	Oval	5060'/ 4050'	Fast	Deciduous	Specimen
Cypress, leyland (cupressocyparis leylandii)	Fine	Pyramidal	5060'/ 2030'	Fast	Conifer	Specimen; screening
Hackberry, sugar (celtis laevigata)	Medium	Upright to rounded	6080'/ 2535'	Medium	Deciduous	Streets; shade
Magnolia, southern (magnolia grandiflora)	Coarse	Horizontal branching, pyramidal	6080'/ 4050'	Slow to medium	Broadleaf evergreen	Specimen; large white flowers
Maple, florida or southern sugar (acer floridanum)	Medium	Oval	4050 ¹ / 2535 ¹	Medium to fast	Deciduous	Shade; orange to red fall color
Maple, red (acer rubrum)	Medium	Rounded	4050'/ 2535'	Medium	Deciduous	Shade; red fall color
Maple, sugar (acer saccharum)	Medium	Oval	6080 ⁷ / 2540 ⁴	Medium to fast	Deciduous	Yellow to reddish fall color; shade
Oak, laurel or darlington (quercus hemisphaerica)	Medium	Rounded	6080'/ 4060'	Medium	Semi- evergreen	Drought-tolerant; street tree
Oak, pin (quercus palustris)	Medium	Pyramidal	5060'/ 2540'	Medium	Deciduous	Shade; specimen
Oak, sawtooth (quercus acutissima)	Medium	Pyramidal	5060'/ 3060'	Fast	Deciduous	Shade; specimen
Oak, scarlet (quercus cocinea)	Medium	Rounded	6080'/ 3040'	Medium	Deciduous	Scarlet fall color; shade
Oak, shumard (quercus shumardii)	Medium	Rounded to oval	6080'/ 5060'	Medium	Deciduous	Scarlet fall color; good street tree

	trees.					
Common name (Botanical name)	Texture	Form	Height/ Spread	Growth rate	Group	Remarks
Ash, white (fraxinus americana)	Fine to medium	Spreading	6070'/ 3040'	Fast	Deciduous	Shade
Beech, american (fagus grandifolia)	Coarse	Rounded	60 8 0'/ 3545'	Medium to fast	Deciduous	Shade
Birch, river (betula nigra)	Medium	Oval	5060 ¹ / 4050 ¹	Fast	Deciduous	Specimen
Cypress, leyland (cupressocyparis leylandii)	Fine	Pyramidal	5060'/ 2030'	Fast	Conifer	Specimen; screening
Hackberry, sugar (celtis laevigata)	Medium	Upright to rounded	60 80 ['] / 2535 [']	Medium	Deciduous	Streets; shade
Magnolia, southern (magnolia grandiflora)	Coarse	Horizontal branching, pyramidal	6080'/ 4050'	Slow to medium	Broadleaf evergreen	Specimen; large white flowers
Maple, florida or southern sugar (acer floridanum)	Medium	Oval	4050'/ 2535'	Medium to fast	Deciduous	Shade; orange to r fall color
Maple, red (acer rubrum)	Medium	Rounded	4050'/ 2535'	Medium	Deciduous	Shade; red fall color
Maple, sugar (acer saccharum)	Medium	Oval	6080'/ 2540'	Medium to fast	Deciduous	Yellow to reddish fall color; shade
Oak, laurel or darlington (quercus hemisphaerica)	Medium	Rounded	6080'/ 4060'	Medium	Semi- evergreen	Drought-tolerant; street tree
Oak, pin (quercus palustris)	Medium	Pyramidal	5060'/ 2540'	Medium	Deciduous	Shade; specimen
Oak, sawtooth (quercus acutissima)	Medium	Pyramidal	5060'/ 3060'	Fast	Deciduous	Shade; specimen
Oak, scarlet (quercus cocinea)	Medium	Rounded	60 8 0'/ 3040'	Medium	Deciduous	Scarlet fall color; shade
Oak, shumard (quercus shumardii)	Medium	Rounded to oval	6080'/ 5060'	Medium	Deciduous	Scarlet fall color; good street tree







THE UTILITIES SHOWN HEREON ARE FOR THE CONTRACTORS CONVENIENCE ONLY. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THESE PLANS. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS SHOWN AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES WITHIN THE LIMITS OF THE WORK. IF THERE ARE ANY DISCREPANCIES THE ENGINEER MUST BE NOTIFIED. ALL DAMAGE MADE TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

Utilities Protection Center, Inc.




YOU DIG GEORGIA CALL US FIRST ! 1-800-282-7411 It's The Law !


24 Hr Emergency Contact: Freddy Teems 770-382-8166

SIGHT DISTANCE REQUIRED 200 FEET OF SIGHT DISTANCE IS REQUIRED FOR THE SPEED LIMIT OF 30 M.P.H.



PORTER STREET





SIGHT DISTANCE - EAST HORIZONTAL SCALE: 1"=20' VERTICAL SCALE: 1"=10'

SIGHT DISTANCE - WEST HORIZONTAL SCALE: 1"=20' VERTICAL SCALE: 1"=10'

STEPHENSON ENGINEERING, INC

> CIVIL ENGINEERING, LAND PLANNING &

DEVELOPMENT CONSULTING P.O. BOX 201088

1130 N. TENNESSEE ST., SUITE D

CARTERSVILLE, GEORGIA 30120 MAIL: STEPHENSONENG@YAHOO.CO

> PHONE : (770)382-7877 FAX: (770)382-3742

ENGINEER GSWCC# 0000020715

THE HOLDER OF THIS DOCUMENT WAI

ALL CLAIMS AGAINST STEPHENSON ENGINEERING INCORPORATED FOR ANY

UNAUTHORIZED CHANGES OR REUSE OI THIS DOCUMENT. THIS DOCUMENT IS A

INSTRUMENT OF SERVICE OF STEPHENSC ENGINEERING INCORPORATED WHO

RETAINS ALL RIGHTS OF COMMON L STATUTE AND COPYRIGHT THERET

K.

NER/DEVELOPE

PROJECT#

15-004

DATE

8-21-18


SHEET TITLE


Site Distance


Plan & Profile


SHEET NO.


.8
















BOTTOM LANDI 2% SLOPE WITH TRANSITION (N
POST MOU SIGN WITH 'VAN ACCE
WHEEL-STOP I TO PREVENT I OVER REQUIR WALKWAY.
PARKING A ACCESS A 2% MAX IN DIRECTIO
RAMP SUR FROM ADJ
ACCI






















EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST STAND ALONE CONSTRUCTION PROJECTS Address: Porter Street Date on Plans:8-21-18 Name&email of person filling out checklist:Greg Bates, email: stephensoneng@yahoo.com TO BE SHOWN ON ES&PC PLAN The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted. (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed) ALL 2 Level II certification number issued by the Commission, signature and seal of the certified design professional. (Signature, seal and Level II number must be on each sheet pertaining to ES&PC plan or the Plan will not be N/A 3 Limits of disturbance shall be no greater than 50 acres at any one time without prior written authorization from the EPD District Office. If EPD approves the request to disturb 50 acres or more at any one time, the plan must include at least 4 of the BMPs listed in Appendix 1 of this checklist.* (A copy of the written approval by EPD must be attached to the plan for the plan to be reviewed.) 4 The name and phone number of the 24-hour local contact responsible for erosion, sedimentation and pollution controls. 5 Provide the name, address and phone number of primary permittee. S Note total and disturbed acreage of the project or phase under construction. 7 Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees. 8 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions. 9 Description of the nature of construction activity. 0 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary. 1 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshlands, etc. which may be affected. C4.1 12 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on page 15 of the permit. C4.1 13 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on page 15 of the permit.* C4.1 14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation."* C4.1 15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measured from the point of wrested vegetation or within 25-feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary C4.1 16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required. Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional."* C4.1 18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as


C4.1			om the site shall be prevented by th prior to land disturbing activities."	e installation of						
C4.1	approved plan does not pro		will be maintained at all times. If fu ntrol, additional erosion and sedime ource."	•						
C4.1	21 Clearly note the statement stabilized with mulch or terr		osed for a period greater than 14 da	ays shall be						
N/A	upstream of and within the with Part III. C. of the Perm	ny construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile ostream of and within the same watershed as, any portion of an Biota Impaired Stream Segment must comply ith Part III. C. of the Permit. Include the completed Appendix 1 listing all the BMPs that will be used for those reas of the site which discharge to the Impaired Stream Segment.*								
N/A	item 22 above) at least six	If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in item 22 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan.*								
C4.1, D2	24 BMPs for concrete washdow of the drum at the construct		chutes, hoppers and the rear of the	vehicles. Washout						
C4.1	25 Provide BMPs for the reme	diation of all petroleum spills	s and leaks.							
C4.1	26 Description of the measures	s that will be installed during	the construction process to contro	l pollutants in storm						
	water that will occur after o	water that will occur after construction operations have been completed.*								
C4.1	27 Description of the practices	7 Description of the practices that will be used to reduce the pollutants in storm water discharges.*								
C4.1	portions of the site (i.e., initi		nce of major activities which disturb storage BMPs, clearing and grubbin al stabilization).							
C4.1	29 Provide complete requirem	ents of inspections and reco	rd keeping by the primary permittee	e.*						
C4.1	30 Provide complete requirem	wide complete requirements of sampling frequency and reporting of sampling results.*								
C4.1	31 Provide complete details for									
C4.1	4		·	location *						
			and analyze the samples from each	nocation.						
C4.1	33 Appendix B rationale for NT		•••							
N/A	34 Delineate all sampling locat storm water is discharged.		tent streams and other water bodies	s into which						
C4.1	 (1) initial sediment storage BMPs, and (3) final BMPs. 	requirements and perimeter For construction sites when grading and drainage BMP	t will be implemented at the constru- control BMPs, (2) intermediate gra e there will be no mass grading and s, and final BMPs are the same, th	ding and drainage the initial perimeter						
ALL	36 Graphic scale and North an	row.								
C2	37 Existing and proposed cont	our lines with contour lines (drawn at an interval in accordance v	with the following:						
	Map Scale	Ground Slope	Contour Intervals, ft.	0.						
	1 inch = 100ft or	Flat 0 - 2%	0.5 or 1							
	larger scale	Rolling 2 - 8%	1 or 2							
		rger scale Rolling 2 - 8% 1 or 2 Steep 8% + 2,5 or 10								

NI / A	
N/A	38 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to
	conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at
	www.gaswcc.org.
N/A	39 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A-2 of the Manual
	for Erosion & Sediment Control in Georgia 2016 Edition.*
N/A	40 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to state waters and any additional
	buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.
N/A	41 Delineation of on-site wetlands and all state waters located on and within 200 feet of the project site.
C6,7	42 Delineation and acreage of contributing drainage basins on the project site.
Attached	43 Provide hydrology study and maps of drainage basins for both the pre- and post-developed conditions.*
C4.1	44 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.
C4.1	45 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without
· · · · ·	erosion. Identify/Delineate all storm water discharge points.
C4.1	46 Soil series for the project site and their delineation.
C4.2-4.4	47 The limits of disturbance for each phase of construction.
C4.1	48 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin,
	retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been achieved. A written justification explaining the decision to use equivalent controls when a sediment basin is not attainable must be included in the plan for each common drainage location in which a sediment basin is not attainable must be included in the plan for each common drainage location in which a sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not attainable must also be given. Worksheets from the Manual included for structural BMPs and all calculations used by the storage design professional to obtain the required sediment when using equivalent controls. When discharging from sediment basins and impoundments, permitees are required to utilize outlet structures that withdraw water from the surface, unless infeasible. If outlet structures that withdraw water from the surface are not feasable, a written justification explaining this decision must be included in the plan.
C4.2-4.4	49 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.
D2	50 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.
D4	51 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of the year that seeding will take place and for the appropriate geographic region of Georgia. *If using this checklist for a project that is less than 1 acre and not part of a common development but within 200 ft of a perennial stream the * checklist items would be N/A. Effective January 1, 2018



POND MAINTENANCE SCHDULES







25 YR STORM

Channel Calculator


Given Input Data:	
Shape	Trapezoidal
Solving for	Depth of Flow
Flowrate	0.0800 cfs
Slope	0.0100 ft/ft
Manning's n	0.0350
Height	12.0000 in
Bottom width	24.0000 in
Left slope	3.0000 ft/ft (V/H
Right slope	3.0000 ft/ft (V/I


Computed Results:

omputed Results.	
Depth	0.7416 in
Velocity	0.6407 fps
Full Flowrate	6.7943 cfs
Flow area	0.1249 ft2
Flow perimeter	25.5634 in
Hydraulic radius	0.7034 in
Top width	24.4944 in
Area	2.3333 ft2
Perimeter	49.2982 in
Percent full	6.1799 %




Ownership of Detention Pond: 1	Residentia	l Gov	ernm	ent	Cor	nmei	cial Oth	her: Light Industrial
								Normal DryX
Subdivision/Development Name: _								et Address: 32 Porter Street
Watershed <u>Satterfield Bra</u>	nch			Sı	ibwat	ershe	2d	
Scoring Breakdown: N/A = Not Applicable N/I = Not Inve 0 = No Problem 1 = Monitor - potential fo * Use comments section to further expla INSPECTION FREQUENCY KEY	or problen	g as nee	eded				S=AFT	equired 3 = Immediate Repair Necessary REMAJOR STORM
INSPECTION ITEMS	N/A	Ν⁄Ι	0	1	2	3	INSPECTION FREQUENCY	COMMENTS
POND COMPONENTS								
1. Embankment and Emergency Spillway								
Adequate vegetation and ground cover							Α	
Embankment material							A	
Animal burrows							A	
Woody Growth or Unauthorized Plantings							Α	
Cracking, bulging, or sloughing of dam							A	
i. Upstream Face							A	
ii. Downstream Face							A	
iii. At or beyond toe upstream							A	
Downstream							A	
iv. Emergency Spillway							A	
Pond, toe & chimney drains clear and functioning							A	
Leaks on downstream face			-	-			Α	
Abutment protection or riprap failures							A	
Visual settlement or horizontal misalignment of top of dam							A	
Emergency spillway clear of dibris			-	-	-	-	A	
Other (specify)							A	
2. Riser and Principal Spillway							A	
Type: Reinforced concrete Corrugated Pipe								
□ Masonry								
Low flow orifice obstructed							A	
Low flow trash rack							A	
i. Debris Removal necessary							A	
ii. Corrosion Control							A	
Weir Trash Rack				1			A	





GRASS CHANNEL MAINTENANCE SCHDULES





100 YR STORM

COMMENTS


Channel Calculator

(Given Input Data:	
	Shape	Trapezoidal
	Solving for	Depth of Flow
	Flowrate	0.4400 cfs
	Slope	0.0100 ft/ft
	Manning's n	0.0350
	Height	12.0000 in
	Bottom width	24.0000 in
	Left slope	3.0000 ft/ft (V/H)
	Right slope	3.0000 ft/ft (V/H)


. 2.1129 in

Computed Results: Depth .. Velocity.

Velocity	1.2138 fps
Full Flowrate	6.7943 cfs
Flow area	0.3625 ft2
Flow perimeter	28.4544 in
Hydraulic radius	1.8344 in
Top width	25.4086 in
Area	2.3333 ft2
Perimeter	49.2982 in
Percent full	17.6075 %



POND - 1 EARTHFILL DAM DETAIL (Hmax = 10 FEET)



POND VOLUME

ELEVATION

748.00

749.00

750.00

751.00

752.00

TOTAL STORAGE

0

740

1,821

3,282

5,519

STAGE

0.00

1.00


3.00


5.00


7.00

personal or property damage Level 1B / Level 2 Certification No(s):

			che	dule	an		pection	Report for ER STRIP FACILITIES
	N/A	N/I	0	ı	2	3	INSPECTION FREQUENCY	COMMENTS
<u>15</u>								
							A,S	
ent							A,S	
e of							A,S	
			-					
					1			
							Α	
esign							A	
							A,S	
							A,S	
							A,S	
							Α	
sent							A	
,en							A	
d to							Α	
	<u> </u>						Α	
of conce	rns receiv	ing a:	(1) (2) (3)			Routi	Monitori ne Repair diate Rep	ng r pair Needed







TEMPORARY DSI STABILIZATION (MULCHING) WHEN SEEDING WILL NOT HAVE A SUITABLE GROWING SEASON TEMPORARY STABILIZATION MAY BE ACCOMPLISHED WITH: STRAW OR HAY TO BE APPLIED AT A DEPTH OF 2 TO 4 INCHES PROVIDING COMPLETE SOIL COVERAGE. WOOD WASTE, BARK, SAWDUST-2-3" DEEP (APPROX. 6-9 TONS/ACRE) 1. DRY STRAW OR HAY SHALL BE APPLIED AT A DEPTH OF 2 TO 4 INCHES PROVIDING COMPLETE SOIL COVERAGE. ONE ADVANTAGE OF THIS MATERIAL IS EASY

SEEDING SCHEDULE

APPLICATION. 2. WOOD WASTE (CHIPS, SAWDUST OR BARK) SHALL BE APPLIED AT A DEPTH OF 2 TO 3 INCHES. ORGANIC MATERIAL FROM THE CLEARING STAGE OF DEVELOPMENT SHOULD REMAIN ON SITE, BE CHIPPED, AND APPLIED AS MULCH. THIS METHOD OF MULCHING CAN GREATLY REDUCE EROSION CONTROL COSTS. 3. POLYETHYLENE FILM SHALL BE SECURED OVER BANKS OR STOCKPILED SOIL MATERIAL FOR TEMPORARY PROTECTION. THIS MATERIAL CAN BE SALVAGED AND RE-USED.



TEMPORARY SEEDING

			Resource													
Species	Broadcast	Rates	Area ³	Sol	BAREAREAS	********	initiale di	2051/051/051		103133123	econtenice.	10111031033	Area lines i		ate	Remarks
								issible								
		Pure Live Seed (PLS) Per 1000 sqft		J	F	м	A	м	J	J	А	s	0	N	D	
BARLEY Hordeum vulagre																
alone	3 bu. (144 lbs)	3.3 lbs	M-L				******	\$22112211221							111111111	14,000 seed per pound. Winter hardy. Use
n mixture	1/2 bu. (24lbs)	0.6 lb	Р													on productive soils.
			с													
LESPEDEZA, ANNUAL Lespedeza striata																
alone	40 lbs	0.9 lb	M-L					•								200 000
in mixture	10 lbs	0.2 lb	Р			-	+									200,000 seed per pound. May volunteer for sev- eral years. Use inoculant EL.
			С			+-										
LOVEGRASS, WEEPING Eragrostis curvula																
alone	4 lbs	0.1 lb	M-L				-									1,500,000 seed per pound. May last for several
in mixture	2 lbs	0.05 lb	Р													years. Mix with Sericea lespedeza.
MILLET, BROWNTOP			С													
Panicum fasciculatum																
alone	40 lbs	0.9 lb	M-L													137,000 seed per pound. Quick dense cover.
in mixture	10 lbs	0.2 lb	P C													Will provide excessive competion in mixtures if seeded at high rate.


Species	Broadcast	Rates	Resource Area ³	2	F	'lani	ting	Dat	es b	iy F
				So	lid lin	es in r	dicat bermi	e opt ssible	imun ə but	ו da ma
		Pure Live Seed PLS) Per 1000								
	Rate Per Acre ²	sqft		J	F	М	A	М	J	J
MILLET, PEARL Pennesetum glaucum										
alone	50 lbs	1.1 lbs	M-L		I BELIERISE	12210121012	10210300		50215215	
			Р							
			С							┢
OATS										
Avena sativa alone	4 bu. (128 lbs)	2.9 lbs	M-L							
in mixture	1 bu. (32 lbs)	2.9 lbs 0.7 lb	P							
in mixture	1 bu. (52 lbs)	0.7 10	C							
			0							
RYE Secale cereale										
alone	3 bu. (168 lbs)	3.9 lbs	M-L						******	-
in mixture	1/2 bu. (28 lbs)	0.6 lb	Р							
			С							
RYEGRASS, ANNUAL										
Lolium temulentum alone	40 lbs	0.9 lb	M-L						8.20122	
alone	40 103	0.3 10	P							
			c							
SUDANGRASS Sorghum sudanese										
alone	60 lbs	1.4 lbs	M-L		01101400	natenten			2115112512	
			Р				<u></u>			\vdash
			С			<u> </u>		<u> </u>		-




PERMANENT SEEDING


TYPE OF SPECIES	YEAR	ANALYSIS OR EQUIVALENT N-P-K	RATE	N TOP DRESSING RATE
1. Cool season grasses	First Second	6-12-12 6-12-12	1500 lbs./ac. 1000 lbs./ac.	50-100 lbs./ac. 1/2/
2. Cool season grasses and	Maintenance First Second	10-10-10 6-12-12 0-10-10	400 lbs./ac. 1500 lbs./ac. 1000 lbs./ac.	30 0-50 lbs./ac. 1/ —
legumes 3. Ground covers	Maintenance First Second	0-10-10 10-10-10 10-10-10	400 lbs./ac. 1300 lbs./ac. 3/ 1300 lbs./ac. 3/	_
4. Pine seedlings	Maintenance First	10-10-10 20-10-5	1100 lbs./ac. one 21-gram pellet per seedling placed in the closing hole	_
5. Shrub Lespedeza	First Maintenance	0-10-10 0-10-10	700 lbs./ac. 700 lbs./ac. 4/	_
6. Temporary cover crops seeded alone	First	10-10-10	500 lbs./ac.	30 lbs./ac. 5/
7. Warm season grasses	First Second Maintenance	6-12-12 6-12-12 10-10-10	1500 lbs./ac. 800 lbs./ac. 400 lbs./ac.	50-100 lbs./ac. 2/6/ 50-100 lbs./ac. 2/ 30 lbs./ac.
8. Warm season grasses and legumes	First Second Maintenance	6-12-12 0-10-10 0-10-10	1500 lbs./ac. 1000 lbs./ac. 400 lbs./ac.	50 lbs./ac./6/

Table 6-5.2- Permanent Cover Crops PLANT, PLANTING RATE, AND PLANTING DATE FOR PERMANENT COVER Solid lines indicate optimum dates, dotted lines indicate Seed (PLS) ate Per Acre² Per 1000 sqft 166,000 seed per pound. Low growing. --Sod forming. Slow to establish. Plant with a alone or with temporary cover 60 lbs 1.4 lbs companion crop. Will spread nto bermuda with other perennials pastures and awns. Mix with Sericea lespe-deza or weeping lovegrass. AHIA, WILMINGTON alone or with temporary 60 lbs 1.4 lb M-L cover with other perennials 30 lbs 0.7 lb P ---Same as above. Hulled seed alone 10 lbs 0.2 lb ,787,000 seed per pound. Quick cover Low growing and sod forming. Full sun. Good for athletic fileds. with other perennials 0.7 lb 6 lbs Unhulled seed Plant with winter annuals. 10 lbs 0.2 lb with temporary cover with other perennials 6 lbs 0.1 lb C - C



GSWCC 2016 Edition





Pure Live Seed (PLS) Per 1000 sqft J F M A M J J A S O N D Image: All of the per Acce ² sqft Image: All of the per Acce ² S G N D Image: All of the per Acce ² S S S O N D Image: All of the per Acce ² S S S O N D Image: All of the per Acce ² S S S S O N D Image: All of the per Acce ² S S <td< th=""></td<>
Rate Per Acre ² sqft J F M A M J J A S O N D 3 bu. (144 lbs) 3.3 lbs C I
1/2 bu. (24 lbs) 0.6 lb m
1/2 bu. (24 lbs) 0.6 lb m
Im 3 bu. (180 lbs) 4.1 lbs M-L
3 bu. (180 lbs) 4.1 lbs M-L 1/2 bu. (30 lbs) 0.7 lb P 15,000 seed per pound. Winter hardy.
1/2 bu. (30 lbs) 0.7 lb P 15,000 seed per pound. Winter hardy.
1 15,000 seed per pound. winter nardy.
1 merecian and a second s
o j
³ M-L represents the Mountain; Blue Ridge; and Ridges and Valleys MLRAs
¹ Temporary cover crops are very competitive and will crowd out perennials if seeded too ² Reduce seeding rates by 50% when drilled.

GSWCC 2016 Edition	Species	Broadcast Rates	Resource Area ³		P	antin	g Dat	es by	/Re	sourc	e A	rea		Remarks
tion				Sol	d line:		ate opi missibl					es ind	cate	
		Pure Live Seed (PLS) Rate Per Acre² Per 1000 sqft		J	FI	M A	м	J	J	A :	s	n c	D	
	BERMUDA SPRIGS Cynodon dactylon													
	Coastal, Common, Midland, or Tift 44	40 cu ft 0.9 cu ft or sod plugs 3' x3'	M-L											A cubic foot contains approximately 650 sprigs. A bushel contains 1.25 cubic fee approximately 800 springs.
	Coastal, Common, of Tift 44		P C											Same as above.
	Tift 78		С											Southern Coastal Plain only
	CENTIPEDE													
	Eremochloa ophuiroides	Block sod only	P											-
			С											Drought tolerant. Full sun or partial sha Effective adjacent to concrete and in cc centrated flow areas. Irrigation is neede until fully established. Do not plant nea pastures. Winterhardy as far as north Athens and Atlanta
	CROWNVETECH Coronilla varia													
6-43	with winter annuals or cool season grasses	15 lbs 0.3 lb	M-L P											100,000 seed per pound. Dense growth Drought tolerant and fire resistant. Attra rose, pink and white blossoms spring to fall. Mix with 30 pounds of Tall fescue o pounds of rye. Inoculate see with M inc lant. Use from North Attanta and North



Species	Broadcast		Resource Area ³		Pla	nting	Dat	es b	y Re	esou	rce	Агеа	2		Remarks
				Soli	d lines		te opt nissibl						indic	ate	
	Rate Per Acre ² F	Pure Live Seed (PLS) Per 1000 sqft		J	FN	I A	м	J	J	А	s	0	N	D	
FESCUE, TALL Festuca arundinacea															
alone	50 lbs	1.1 lb	M-L						901010		588583				227,000 seed per pound. Use alone only better sites. Mix with perennial lespeded or Crownvetch. Apply topdressing in sprii
with other perennials	30 lbs	0.7 lb	Р												following fall plantings. Not for heavy use areas or athletic fields.
KUDZU Pueraria thumbergiana															
Plants or crowns	3' - 7' ap	part	ALL			-									Rapid and vigorous growth. Excellent in gully erosion control. Will climb. Good livestock forage.
LESPEDEZA SERICEA Lespedeza cuneata															
scarified	60 lbs	1.4 lb	M-L P C M-L P			-		 							350,000 seed per pound. Widely adapted Low maintenace. Mix with Weeping loveg rass, Common bermuda, bahia, or tall fescue. Takes 2 to 3 years to become full; established. Excellent on roadbanks. Inor late seed with EL inoculant.
unscarified	75 lbs	1.7 lb	С				+	†							Mix with Tall fesue or winter annuals.
seed- bearing hay	3 tons	1338 lbs	M-L P C									_			Cut when seed mixture is mature, but be- fore, it shatters. Add Tall fescue or winter annuals.

Note: Construction schedule is a general time	eline from date	e the land	l disturba	ance peri	nit is issi	led.
ACTIVITY	Month 1	Month 2	Month 3	Month 4	Month 5	Month
COMMENCEMENT OF CONSTRUCTION	4					
INITIAL EROSION CONTROL BMP INTSALLATION						
CLEARING GRUBBING & GRADING						
INTERMEDIATE EROSION CONTROL BMP'S						
GRASSING						
MAINTAIN SEDIMENT CONTROL MEASURES						
INSTALL UNDERGROUND UTILITIES						
INSTALL PAVING						
BUILDING CONSTRUCTION						
FINAL LANDSCAPING						
FINAL PHASE OF ERO. AND SED. CONTROL PLAN						
COMPLETION OF CONSTRUCTION						

n sand dunes.

Grows similar to Tall fescue

For very wet sites. May clog channels. Dig

Grows well on coastal sand dunes, borrow areas, and gravel pits. Provides winter cover for wildlife. Mix with Sericea lespedeza except

sprigs from local sources. Use along river banks and shorelines.

STRUCTURAL PRACTICES

Co	CONSTRUCTION EXIT	(LABEL)	A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.
(Sdl -S	SEDIMENT BARRIER	(INDICATE TYPE)	A barrier to prevent sediment from leaving the construction site. It may be sandbags,bales or straw or hay, brush,logs and poles,gravel,or a sedi- ment fence. The barriers are usually temporary and inexpensive.

VEGETATIVE MEASURES

Dsl	DISTURBED AREA STABILIZATION (MULCHING ONLY)		Ds1	Establishing temporary protection for disturbed areas where seeding may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (TEMPORARY SEEDING)		Ds2	Establishing temporary vegetative cover with fast growing seedings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (PERMANENT VEGETATION)	1 Cr Cry 1 Cr Cry 1 2 Cr Cry 1 2 Cr Cry 1 2 Cry 1	Ds3	Establishing permanent vegetative cover such as trees,shrubs,vines, grasses,sod,or legumes on disturbed areas.

DSI NOTE: TEMPORARY STABILIZATION (MULCHING ONLY) WHEN SEEDING WILL NOT HAVE A SUITABLE GROWING SEASON MAY BE ACCOMPLISHED WITH: STRAW OR HAY-2.5 TONS/ACRE WOOD WASTE, BARK, SAWDUST-2-3* DEEP (APPROX. 6-9 TONS/ACRE)



INSTALLATION

DISTURBED AREA STABILIZATION (WITH SODDING)

<u>SOIL PREPARATION</u> BRING SOIL SURFACE TO FINAL GRADE. CLEAR SURFACE OF TRASH, WOODY DEBRIS, STONES AND CLODS LARGER THAN I'. APPLY SOD TO SOIL SURFACES ONLY AND NOT FROZEN SURFACES, OR GRAVEL TYPE SOILS. TOPSOIL PROPERTY APPLIED WILL HELP GUARANTEE A STAND, DON'T USE TOPSOIL RECENTLY TREATED WITH HERBICIDES OR SOIL STERILANTS. MIX FERTILIZER INTO SOIL SURFACE. FERTILIZE BASED ON SOIL TESTS OR TABLE 6-6.1 BELOW:

FERTILIZER REQUIREMENTS									
FERTILIZER	FERTILIZER RATE	FERTILIZER RATE	SEASON						
TYPE	(LBS/ACRE)	(LBS/SQ. FT.)							
10-10-10	1000	0.025	FALL						

AGRICULTURAL LIME SHOULD BE APPLIED BASED ON SOIL TESTS OR AT A RATE OF 1 TO 2 TONS PER ACRE.

LAY SOD WITH TIGHT JOINTS AND IN STRAIGHT LINES. DON'T OVERLAP JOINTS. STAGGER JOINTS AND DO NOT STRETCH SOD. ON SLOPES STEEPER THAN 3:1, SOD SHOULD BE ANCHORED WITH PINS OR OTHER APPROVED METHODS. INSTALLED SOD SHOULD BE ROLLED OR TAMPED TO PROVIDE GOOD CONTACT BETWEEN SOD AND SOIL IRRIGATE SOD AND SOIL TO A DEPTH OF 4' IMMEDIATLEY AFTER INSTALLTION. SOD SHOULD NOT BE CUT OR SPREAD IN EXTREMELY WET OR DRY WEATHER. IRRIGATION SHOULD BE USED TO SUPPLEMENT RAINFALL FOR A MINIMUM OF 2-3 WEEKS.

MATERIAL SOD SELECTED SHOULD BE CERTIFIED. SOD GROWN IN THE GENERAL AREA OF THE PROJECT IS DESIRABLE.

MULCH IS REQUIRED FOR ALL PERMANENT VEGETAION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. SELECT THE MULCHING MATERIAL FROM THE FOLLOWING AND APPLY AS INDICATED: 1. DRY STRAW OR DRY HAY OF GOOD QUALITY ADN FREE OF WEED SEEDS CAN BE USED. DRY STRAW SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. DRY HAY SHALL BE APPLIED AT A

RATE OF 2.5 TONS PER ACRES. 2. WOOD CELLULOSE MULCH OR WOOD PULP FIBER SHALL BE USED WITH HYDRAULIC SEEDING. IT SHALL BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE. DRY STRAW OR DRY HAY SHALL BE APPLIED (AT THE RATE INDICATED ABOVE) AFTER HYDRAULIC SEDDING. 3. ONE THOUSAND POUNDS OF WEED CELLULOSE OR WOOD PULP FIBER, WHICH INCLUDES A TACKIFIER SHALL BE USED WITH HYDRAULIC SEEDING ON SLOPES 3/4:1 OR STEEPER. 4. SERICEA LESPEDEZA HAY CONTAINING MATURE SEED SHALL BE APPLIED AT A RATE OF THREE TONS PER ACRE. 5. PINE STRAW OR PINE BARK SHALL BE APPLIED AT A THICKNESS OF 3 INCHES FOR BEDDING PURPOSES. OTHER SUITABLE MATERIALS IN SUFFICIENT QUANTITY MAY BE USED WHERE

ORNAMENTALS OR OTHER GROUND COVERS ARE PLANTED. THIS IS NOT APPROPRIATE FOR SEEDED AREAS. 6. WHEN USING TEMPROARY EROSION CONTROL BLANKETS OR BLOCK SOD, MULCH IS NOT REOUIRED. 7. BITUMINOUS TREATED ROVING MAY BE APPLIED ON PLANTED AREAS ON SLOPES, IN DITCHES

OR DRY WATERWAYS TO PREVENT EROSION. BITUMINOUS TREATED ROVING SHALL BE APPLIED WITHIN 24 HOURS AFTER AN AREA HAS BEEN PLANTED. APPLICATION RATES AND MATERIALS MUST MEET GEORGIA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.

